

From: ["Brooks, Karl" </O=EXCHANGELABS/OU=EXCHANGE ADMINISTRATIVE GROUP \(FYDIBOHF23SPDLT\)/CN=RECIPIENTS/CN=78AC91F4DB6D44F58424B504D5AA3C7D-BROOKS, KARL>](#)

To: [Tapia](#)  
[Cecilia:Hammerschmidt](#)  
["Ron; Hague"](#)  
[Mark;](#)

CC:

Date: 1/13/2014 6:25:56 AM

Subject: Fw: WLL Area 1 Heating Event

Attachments: [40056510.pdf](#)  
[40241235.pdf](#)

---

Pls revw and draft response for my signature.

Tx

Property of the U.S EPA. If found please contact the EPA call center at 1-866-411-4EPA, Option 1.

---

**From:** Harvey Ferdman <HarveyFerdman@aol.com>  
**Sent:** Monday, January 13, 2014 12:18:15 AM  
**To:** Brooks, Karl; Tappia.Cecilia@epa.gov; Hatch, Sarah  
**Cc:** Bill.Otto@house.mo.gov; MOMcNeil,Margo; Christopher.Nagel@dnr.mo.gov; Shawn.Muenks@dnr.mo.gov; MATT LAVANCHY; Todd.Thalhamer@CalRecycle.ca.gov; Kerry\_DeGregorio@Blunt.Senate.gov; Joeana\_Middleton@McCaskill.Senate.Gov; Douglas Clemens; 'Terrie Boguski'  
**Subject:** WLL Area 1 Heating Event

Karl,  
Thank you for your interest in the research our community has been doing regarding the West Lake and Bridgeton Landfills.

In our last conversation, you requested that I forward any information I was able to assemble regarding hazards of leaving PVC liners in the boring holes in Area 1 during the work that is scheduled to begin this week.

Please review the following.

- Item 1: Boring showing elevated sub-surface temperature in Area 1.
- Item 2: Email statement from a recognized landfill expert who has been consulting on the SSE in the Bridgeton Landfill in which he raises cautions about leaving the PVC liners in


place.

Item 3: Documented presence of petroleum soaked soils and possible “shock sensitive” materials in Area 1.

I continue to be concerned about the PVC pipes providing a possible oxygen paths in Area 1. I believe this information supports my concern. I look forward to your reply.

**Item 1:**

On the last state and local officials update conference call, you mentioned that a key reason you were OK with leaving the PVC pipes in place is because you were told that there have never been any high temperature readings in Area 1. I’m sorry this may contradict the information you were told and I hope you find the following data helpful. This is from pdf page 22 of the attached report 40056510.pdf. It shows a temperature of 140 degrees at 56 feet deep in Area 1 boring logs. According to our first responders who have been studying landfill fires and sub-surface events and their management, any reading over 131 degrees at depth is considered a possible sub-surface smolder event and merits further testing and monitoring. I have also inquired to our citizen researchers regarding their claim that there was a fire in the proximity of this well after the boring sample was taken that apparently reached the surface before being controlled by pouring a slurry into the area. I will forward documentation on that event as soon as I am able to confirm it. In the meantime, I hope you and your team find this information useful.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-110		Project No./Name 07.0803035.003.002	Page: 2 of 2
Start/Finish Date 9/6/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Ground Surface Elevation:	Area 1 484.41 (Planned Boring
Driller Bruce Murphy		Northing: Easting:	1068889.01 location, not 516645.03 surveyed)
Drilling Equipment LDH-80T Drilling Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD, Solid Auger	Sample Method Grab from Augers	T.D. Borehole 56'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
55	WL-110 55'	Background (0.02-0.04)	50.0-56.0' <u>Native Alluvium</u> : dark gray, clayey silt; moist, very warm.  @ 56.0' sample had a temperature of 140° F  Boring terminated at 56.0'
60	WL-110 56'	Background (0.02-0.04)	

**Item 2:**

From: Todd Thalhamer

Date: 01/09/2014 3:38 PM (GMT-06:00)

To: MATT LAVANCHY

Subject: RE: Fwd: WLL Trench Piping Issue

Matt,

Sorry for the delayed response, my kids gave me a nasty bug that I am now just coming out to see the world again.

While the methods the landfill are proposing are acceptable, you are correct with the potential outcome. These pipes can be direct conduits to an sse. I have seen these types of investigative methods add to problems over time. My questions are

1. Given the potential for an sse, would one want to you use steel piping?
2. Past maintenance issues have shown the If is unstable in areas, what type of seal is going to be place are the pipe and how will it be maintained.?
3. Will the piping be added to an weekly inspection list?
4. Will the piping be protected from equipment?
5. One has to maintain these pipes and ensure they don't become a pathway for oxygen.

Sent from my T-Mobile 4G LTE Device

----- Original message -----

From: MATT LAVANCHY

Date: 01/08/2014 4:27 PM (GMT-08:00)

To: Todd Thalhamer

Cc: TERRY LOEHRER

Subject: Fwd: WLL Trench Piping Issue

Todd, not sure if this was sent to you already but I think your expert opinion in this should be heard. My opinion would just be an opinion, but allowing a means for oxygen to be drawn into that part of the landfill will only support the combustion process of any sse that makes its way there.

Matt

Sent from my Verizon Wireless 4G LTE Smartphone

----- Original message -----

From: Harvey Ferdman

Date: 01/08/2014 4:38 PM (GMT-06:00)

To: MATT LAVANCHY ,Todd.Thalhamer@CalRecycle.ca.gov

Subject: WLL Trench Piping Issue

Matt and Todd,

Todd, I mentioned this issue to Matt and he asked me to send this email:

On a briefing conference call today by the EPA, they said that the next phase of building a barrier in Area 1 at West Lake Landfill is to do core sampling using a sonic drill. The holes left from the drilling are going to be fitted with PVC piping and a removable cap so they can access them in the future if needed. The deepest they expect to go is 80 feet..

My question and concern is: is it safe to leave multiple pipe paths deep into this dump that can potentially allow oxygen infiltration? I asked the EPA if a dump expert had reviewed this part of the plan, and, after a lot of dancing, the answer was effectively a no, as they did not see any reason for the concern that I raised. My fear is that someone in the future (or some natural act, like a tornado, earthquake, or animal) may damage a cap or two and open up a pathway for oxygen to make it deep within this dump and start a smolder event or fire, and the potential for odor releases.

Should I be concerned about this?

---

**Item 3:**

In the presence of petroleum soaked soil, can this start an SSE during the construction of the Isolation Barrier?

Note: Page 18 of document 40241235.pdf – VII Waste related information:


**Waste Characteristics check-marked are: 2. Ignitable 3. Radioactive 5. Toxic and page 19 - Item 5 - Incompatible Wastes** and presence of flammable and “shock sensitive” materials

Document 40056510:

1. Area 1 Boring Hole Samples
  - a. WL-101 at 5 ft discolored with petroleum odor OVM readings >10x background
  - b. Many other borings show similar presence of petroleum

Note: Page 18 – VII Waste related information: **Waste Characteristics check-marked are: 2. Ignitable 3. Radioactive 5. Toxic and page 19 - Item 5 - Incompatible Wastes**

2. Area 1 – An underground diesel tank is located beneath the asphalt paved area in the west portion of Area 1. The tank is no longer in use but has not be removed because it is within the boundaries of Area 1 and has leaked into the surrounding area – another tank leaked prior to removal in 1993 resulting in “floating product thickness as high as 3.7 feet has been observed” according to the following document:



Harvey Ferdman

Policy Advisor to

Missouri State Representative Bill Otto, District 70

St. Louis, MO 63017

314-469-0595

314-761-5100 (cell)

**ENGINEERING MANAGEMENT SUPPORT INC.**

12335 West 53<sup>rd</sup> Ave. Suite 201  
Arvada, CO 80002

Telephone (303) 940-3426  
Telecopier (303) 940-3422

Site: West Lake Landfill  
ID #: M00079900932  
Break: 3.3 out  
Other: McLaren / Hart  
2-25-97

February 25, 1997

Mr. Jalal El-Jayyousi  
State of Missouri  
Department of Natural Resources  
Division of Environmental Quality  
P.O. Box 176  
Jefferson City, MO 65102-0176

Mr. John Niffenegger  
Sverdrup  
13723 Riverport  
Maryland Heights, MO 63043

**RECEIVED**

**MAR 03 1997**

**SUPERFUND DIVISION**

**SUBJECT : Copies of Boring Logs and Aquifer Testing Results  
West Lake Landfill Operable Unit 1  
Bridgeton, Missouri**

Dear Messrs. El-Jayyousi and Niffenegger,

Mr. Steve Kinser of USEPA Region VII requested that we forward copies of pertinent appendices from two recent McLaren/Hart reports on the subject project for your use. Specifically, the following information is enclosed:

- From the Soil Boring/Surface Soil Investigation Report, West Lake Landfill Areas 1 & 2 (McLaren/Hart, November 26, 1996):
  - Area 1 Boring Logs
  - Area 2 Boring Logs
  - Area 1 Soil Boring Downhole Gamma Logs
  - Area 2 Soil Boring Downhole Gamma Logs
  - PVC Boring Downhole Gamma Logs
- From the Groundwater Conditions Report, West Lake Landfill Areas 1 & 2 (McLaren/Hart, November 26, 1996):
  - Boring Logs and Well Construction Details
  - Aquifer Testing Results



40056510  
SUPERFUND RECORDS

Messrs. El-Jayyousi and Niffenegger

02/25/97

Page 2

If you have any questions please call me.

Sincerely,

**ENGINEERING MANAGEMENT SUPPORT, Inc.**



Robert T. Jelinek, P.E.

Enclosures

cc: (w/ enclosures):

Steve Kinser, USEPA Region VII

(w/o enclosures):

Doug Borro - Laidlaw Waste Systems Inc.

Ward Herst - Golder Associates

Michael Hockley - Spencer Fane Britt & Browne

Steve Landau - Cotter Corporation

Charlotte Neitzel - Holme Roberts & Owen

James Wagoner II - U. S. Department of Energy

William Werner - Stolar Partnership

W.E. Whitaker - Rock Road Industries

*Prepared for:*

The West Lake Respondent Group

*Prepared by:*


McLaren/Hart Environmental Engineering Corporation  
1000 Town Center, Suite 600  
Southfield, Michigan 48075

Prepared by:



David J. Heinze  
Senior Associate Engineer

Reviewed by:



Bruce E. Ehleringer  
Managing Principal Geoscientist

November 26, 1996

Project No. 07.0803035

RECEIVED  
MAR 03 1997  
SUPERFUND DIVISION

SOIL BORING/SURFACE SAMPLE  
INVESTIGATION REPORT  
WEST LAKE LANDFILL  
RADIOLOGICAL AREAS 1 AND 2  
BRIDGETON, MISSOURI



Figure 3-53	Soil Analytical Data, Priority Pollutant Metals, Area 1
Figure 3-54	Soil Analytical Data, Priority Pollutant Metals, Area 2
Figure 3-55	Soil Analytical Data, Total Petroleum Hydrocarbons, Area 1
Figure 3-56	Soil Analytical Data, Total Petroleum Hydrocarbons, Area 2
Figure 3-57	Soil Analytical Data, Polychlorinated Biphenyl, Area 1
Figure 3-58	Soil Analytical Data, Polychlorinated Biphenyl, Area 2
Figure 3-59	Perched Water Uranium-238 Decay Series Analytical Data
Figure 3-60	Perched Water Uranium-235 Decay Series Analytical Data


## **APPENDICES**

Appendix A	Background Soil Sampling Analytical Results
Appendix B	Boring Logs
Appendix C	Soil Sampling Analytical Results
Appendix D	Letter from Quanterra Regarding Soil Analytical Procedural Error
Appendix E	Perched Water Sampling Analytical Results
Appendix F	Soil Priority Pollutant and Contingency Soil Sampling Analytical Results
Appendix G	Perched Water Priority Pollutant and Leachate Indicator Parameter Sampling Analytical Results
Appendix H	Downhole Logs
Appendix I	QA/QC Review

---

## **Area 1 Boring Logs**

---

Soil Boring Log		 <b>McLaren/Hart</b>	
Boring No. WL-101		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/4/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 1 Ground Surface Elevation: 456.5	
Driller Max Tinnin		Northing: 1069549.55 Easting: 516317.21	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5' Continuous Sampler	T.D. Borehole 25'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-101 5'	Background (0.02-0.04)	0.0-17.0' <u>Landfill Debris</u> : soil consisting of clayey silt to sandy silt, and crushed rock; no trashy debris encountered; dry to moist.  @ 5' soil discolored with petroleum odor; OVM readings greater than 10 X background.
10	WL-101 10'	Background (0.02-0.04)	
15	WL-101 15'	Background (0.02-0.04)	
20	WL-101 20'	Background (0.02-0.04)	17.0-25.0' <u>Native Alluvium</u> : grayish brown, slightly silty, plastic clay grading to dark gray, very fine-grained sand; moist to wet.  @ 23.0' wet Boring terminated @ 25'
25	WL-101 25'	Background (0.02-0.04)	


Notes:

Radiological samples collected at 5 and 20 feet below ground surface.

Non-radiological samples collected at 5 and 25 feet below ground surface; contingency sampling.

Perched water not encountered during boring activities.

Groundwater encountered at 23 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-102		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/4/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 1 Ground Surface Elevation: 462.8	
Driller Max Timm		Northing: 1069260.46 Easting: 515974.05	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5' Continuous Sampler	T.D. Borehole 34'	Well Installed? None installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (nR/hr)	Description
5	WL-102 5'	Background (0.02-0.04)	0.0-23.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, glass, and wire; soil consisting of olive gray silt and dark gray, silty, plastic clay to grayish brown, silty sand and crushed rock; dry to moist.
10	None Taken	Background (0.02-0.04)	
15	None Taken	Background (0.02-0.04)	
20	None Taken	Background (0.02-0.04)	
25	WL-102 25'	Background (0.02-0.04)	23.0-34.0' <u>Native Alluvium</u> : grayish brown, slightly silty, plastic clay grading to dark gray, fine-grained sand; moist.
30	WL-102 30'	Background (0.02-0.04)	
35	WL-102 35'	Background (0.02-0.04)	
			Auger refusal @ 34'

Notes:

Radiological samples collected at 5 and 15 feet below ground surface; downhole logging indicated elevated gamma readings from 2.0 - 4.0'.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater not encountered during boring activities.

# Soil Boring Log




**McLaren  
Hart**

<b>Boring No.</b> WL-105A		<b>Project No./Name</b> 07.0803035.003.002	<b>Page:</b> 1 of 2
<b>Start/Finish Date</b> 8/8/95 / 8/9/95		<b>Site Name and Location</b> West Lake Landfill; Bridgeton, Missouri	
<b>Drilling Contractor</b> Hart Environmental Drilling		<b>Boring Location:</b> Area 1	
<b>Driller</b> Max Timin		<b>Ground Surface Elevation:</b> 467.2	
		<b>Northing:</b> 1069136.26	
		<b>Easting:</b> 515871.62	
<b>Drilling Equipment</b> CME-55 Drill Rig, Hollow Stem Augers		<b>McLaren/Hart Geologist/Office</b> Tim Biggs / St. Louis	
<b>Bit Size/Type</b> 4 1/4" ID; 8 1/4" Hole	<b>Sample Method</b> 5' Continuous Sampler	<b>T.D. Borehole</b> 109'	<b>Well Installed?</b> D-3

## Remarks:

Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description
5	None Taken	None Taken	0.0-30.0' <u>Landfill Debris</u> : trashy debris consisting of cloth, wood, rope, and plastic; soil consisting of brown and gray silt, and crushed rock; dry to moist.
10	WL-105A 10'	None Taken	
15	None Taken	None Taken	
20	None Taken	None Taken	
25	None Taken	None Taken	
30	WL-105A 30'	None Taken	
35	None Taken	None Taken	30.0-60.0' <u>Native Alluvium</u> : dark gray clayey silt grading to fine to coarse-grained sand and gravel; wet.  @ 30' wet
40	None Taken	None Taken	
45	WL-105A 47'	Background (0.04-0.06)	
50	None Taken	None Taken	
55	None Taken	None Taken	
60	None Taken	None Taken	

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-105A		Project No./Name 07.0803035.003.002	Page: 2 of 2
Start/Finish Date 8/8/95 / 8/9/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 1 Ground Surface Elevation: 467.2	
Driller Max Timmin		Northing: 1069136.26 Easting: 515871.62	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5' Continuous Sampler	T.D. Borehole 109'	Well Installed? D-3
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
70	None Taken	None Taken	60.0-109.0' Native Alluvium: dark gray clayey silt grading to fine to coarse-grained sand and gravel; wet.
75	None Taken	None Taken	
80	None Taken	None Taken	
85	None Taken	None Taken	
90	None Taken	None Taken	
95	None Taken	None Taken	
100	None Taken	None Taken	
105	None Taken	None Taken	
110	None Taken	Background	Auger refusal @ 109.0' (bedrock)

Notes:

Radiological samples collected at 10 and 30 feet below ground surface; downhole logging indicated elevated gamma readings from 0.5-11.0'.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater encountered at 30 feet below ground surface.

# Soil Boring Log




**McLaren  
Hart**

Boring No. <b>WL-105B</b>		Project No./Name 07.0803035.003.002		Page: 1 of 2
Start/Finish Date 8/10/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri		
Drilling Contractor Hart Environmental Drilling		Boring Location: Farmers Field		
Driller Max Timm		Ground Surface Elevation: 466		
		Northing: 1069148.42		
		Easting: 515889.50		
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers			McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Btt Size/Type 4 1/4" ID; 8 1/4" Hole		Sample Method 5' Continuous Sampler		T.D. Borehole 79'
				Well Installed? 1-4

## Remarks:

Depth (ft)	Sample ID #	Gelger Reading (inR/hr)	Description
5	None Taken	None Taken	0.0-30.0' <u>Landfill Debris</u> : trashy debris consisting of cloth, wood, rope, and plastic; soil consisting of brown and gray silt, and crushed rock; dry to moist.
10	None Taken	None Taken	
15	None Taken	None Taken	
20	None Taken	None Taken	
25	None Taken	Background	
30	WL-105B 30'	Background (0.04-0.06)	@30' wet
35	WL-105B 35'	Background (0.04-0.06)	30.0-55.0' <u>Native Alluvium</u> : dark gray clayey silt grading to fine to coarse-grained sand and gravel; wet.
40	WL-105B 40'	Background (0.04-0.06)	
45	None Taken	None Taken	
50	None Taken	None Taken	
55	None Taken	None Taken	

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-105C		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/15/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 1	
Driller Max Tinnin		Ground Surface Elevation: 465.7	
		Northing: 1069155.84	
		Easting: 515901.03	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5' Continuous Sampler	T.D. Borehole 43'	Well Installed? S-5
Remarks:			
Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description
5	None Taken	0.7	0.0-30.0' <u>Landfill Debris</u> : trashy debris consisting of cloth, wood, rope, and plastic; soil consisting of brown and gray silt, and crushed rock; dry to moist.
10	None Taken	0.2	
15	None Taken	Background (0.02-0.04)	
20	None Taken	Background (0.02-0.04)	
25	None Taken	Background (0.02-0.04)	
30	None Taken	Background (0.02-0.04)	@ 30' wet
35	None Taken	Background (0.02-0.04)	30.0-43.0' <u>Native Alluvium</u> : dark gray clayey silt grading to fine to coarse-grained sand and gravel; wet.
40	None Taken	Background (0.02-0.04)	
45	None Taken	Background (0.02-0.04)	
Boring terminated @ 43.0'			

Notes:


Radiological samples not collected during boring activities; downhole logging indicated elevated gamma readings from 1.5-5.5'

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater encountered at 30 feet below ground surface.



<b>Soil Boring Log</b>				<b>McLaren Hart</b>	
Boring No. WL-106		Project No./Name 07.0803035.003.002		Page: 1 of 1	
Start/Finish Date 8/11/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri			
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 1		Ground Surface Elevation: 465.4	
Driller Max Tinnin		Northing: 1069301.64		Easting: 516082.18	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers			McLaren/Hart Geologist/Office Tim Biggs / St. Louis		
Bit Size/Type 4 1/4" ID; 8 1/4" Hole		Sample Method 5' Continuous Sampler		T.D. Borehole 20'	Well Installed? None Installed
Remarks:					
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description		
5	None Taken	Background (0.02-0.04)	0.0-20.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, glass, and wire; soil consisting of dark gray silt to clayey silt, and crushed rock; dry to moist.  Boring terminated @ 20.0'		
10	None Taken	Background (0.02-0.04)			
15	None Taken	Background (0.02-0.04)			
20	None Taken	Background (0.02-0.04)			


**Notes:**

Radiological samples not collected during boring activities; downhole logging indicated elevated gamma readings from 2.5-5.0'.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater not encountered during boring activities.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-106A		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/11/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 1	Ground Surface Elevation: 462.8
Driller Max Timmin		Northing: 1069317.25	Easting: 516061.92
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5" Continuous Sampler	T.D. Borehole 35'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	None Taken	0.5-1.0	0.0-24.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, glass, and wire; soil consisting of dark gray silt to clayey silt, and crushed rock; dry to moist.
10	None Taken	0.5-1.0	
15	None Taken	0.5-1.0	
20	None Taken	0.05-0.10	
25	W1-106A 25'	Background (0.06-0.10)	24.0-35.0' <u>Native Alluvium</u> : dark gray, silty, plastic clay grading to dark gray, very fine-grained sand; moist to wet.
30	W1-106A 30'	Background (0.06-0.10)	@ 30' wet
35	W1-106A 35'	Background (0.06-0.10)	Boring terminated @ 35.0'


Notes:

Radiological samples collected at 5 and 25 feet below ground surface; downhole logging indicated elevated gamma readings from 0.0-1.0'

Non-radiological samples collected at 30 feet below ground surface; priority pollutant and priority pollutant duplicate collected and analyzed.


Perched water not encountered during boring activities.

Groundwater encountered at 30 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-107		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/5/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor		Boring Location: Area 1	
Drilling Service Company		Ground Surface Elevation: 486.1	
Driller Bruce Murphy		Northing: 1068909.52	
		Easting: 516254.31	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Auger	T.D. Borehole 52'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description
5	WL-107 5'	Background (0.02-0.04)	0.0-51.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, paper, rubber, yard waste, cloth, brick, carpeting, glass and wire; soil consisting of olive brown silt to grayish brown and dark gray clayey silt, and rock; dry to wet.
10	WL-107 10'	Background (0.02-0.04)	
15	WL-107 15'	Background (0.02-0.04)	
20	WL-107 20'	Background (0.02-0.04)	
25	WL-107 25'	Background (0.02-0.04)	
30	WL-107 30'	Background (0.02-0.04)	
35	WL-107 35'	Background (0.02-0.04)	
40	WL-107 40'	Background (0.02-0.04)	
45	WL-107 45'	Background (0.02-0.04)	51.0-52.0' <u>Native Alluvium</u> : dark gray, silty, fine-grained sand; wet. @ 51' wet Boring terminated @ 52.0'.
50	WL-107 50'	Background (0.02-0.04)	
55	WL-107 52'	Background (0.02-0.04)	


Notes:


Radiological samples collected at 5 and 51 feet below ground surface.  
 Non-radiological samples not collected during boring activities.  
 Perched water not encountered during boring activities.  
 Groundwater encountered at 51 feet below ground surface.

<b>Soil Boring Log</b>				<b>McLaren Hart</b>	
<b>Boring No.</b> WL-108		<b>Project No./Name</b> 07.0803035.003.002		<b>Page:</b> 1 of 1	
<b>Start/Finish Date</b> 9/5/95		<b>Site Name and Location</b> West Lake Landfill; Bridgeton, Missouri			
<b>Drilling Contractor</b> Drilling Service Company		<b>Boring Location:</b> Area 1		<b>Ground Surface Elevation:</b> 472.5	
<b>Driller</b> Bruce Murphy		<b>Northing:</b> 1069144.21		<b>Easting:</b> 516379.68	
<b>Drilling Equipment</b> LDH-80T Drill Rig, Large Diameter Auger			<b>McLaren/Hart Geologist/Office</b> Tim Biggs / St. Louis		
<b>Bit Size/Type</b> 24" OD Solid Auger		<b>Sample Method</b> Grab from Auger		<b>T.D. Borehole</b> 22'	<b>Well Installed?</b> None Installed
<b>Remarks:</b>					
<b>Depth (ft)</b>	<b>Sample ID #</b>	<b>Gelger Reading (mR/hr)</b>	<b>Description</b>		
5	WL-108 5'	Background (0.02-0.04)	0.0-22.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, paper, rubber, metal, and cardboard; soil consisting of olive brown to dark gray silt, and rock; dry to wet.  @ 12' wet  Boring abandoned @ 22.0'		
10	None Taken	None Taken			
15	None Taken	None Taken			
20	None Taken	None Taken			
25	None Taken	None Taken			

**Notes:**

Radiological sample collected at 5 feet below ground surface.  
Non-radiological grab sample collected from perched water.  
Perched water encountered at 12 feet below ground surface.  
Groundwater not encountered during boring activities

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-109B		Project No./Name 07.0803035.003.002	Page: 1 of 2
Start/Finish Date 9/7/95 / 10/24/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 1	
Drilling Service Company		Ground Surface Elevation: 484.5	
Driller Max Tinnin		Northing: 1068947.16	
Bruce Murphy		Easting: 516523.17	
		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers LDH-80T Drill Rig, Large Diameter Auger			
Bit Size/Type 4 1/4" ID 8 1/4" Hole 24" OD Solid Auger		Sample Method Continuous Sampler Grab from Auger	T.D. Borehole 59' Well Installed? D-14
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	None Taken	None Taken	0.0-49.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, brick, paper, wire, rubber, metal, yard waste, and carpeting; soil consisting of olive brown to dark gray silt, gray to black silty clay, and crushed rock; dry to moist; warm.
10	None Taken	None Taken	
15	None Taken	None Taken	
20	None Taken	None Taken	
25	None Taken	None Taken	
30	None Taken	None Taken	
35	None Taken	None Taken	
40	None Taken	None Taken	
45	None Taken	None Taken	@ 45.0' sample had temperature of 116°F

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-109B		Project No./Name 07.0803035.003.002	Page: 2 of 2
Start/Finish Date 10/24/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 1	
Drilling Service Company		Ground Surface Elevation: 484.5	
Driller Max Tinnin Bruce Murphy		Northing: 1068947.16 Easting: 516523.17	
		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers LDH-80T Drill Rig, Large Diameter Auger			
Bit Size/Type 4 1/4" ID 8 1/4" Hole 24" OD Solid Auger	Sample Method Continuous Sampler Grab from Auger	T.D. Borehole 59'	Well Installed? D-14
Remarks:			
Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description
50	None Taken	None Taken	49.0-59.0' Native Alluvium: dark gray, clayey and silty, very fine-grained sand; moist; warm.
55	None Taken	None Taken	
60	WL-109B 59'	None Taken	
Auger refusal @ 59.0' (bedrock)			

Notes:

Radiological samples not collected during boring activities.  
 Non-radiological samples not collected during boring activities.  
 Perched water not encountered during boring activities.  
 Groundwater not encountered during boring activities.

# Soil Boring Log



**McLaren  
Hart**

Boring No.  
WL-109C

Project No./Name  
07.0803035.003.002

Page:  
1 of 2

Start/Finish Date  
9/12/95

Site Name and Location  
West Lake Landfill; Bridgeton, Missouri

Drilling Contractor  
Drilling Service Company

Boring Location: Area 1  
Ground Surface Elevation: 483.9

Driller  
Bruce Murphy

Northing: 1068961.12  
Easting: 516528.43

Drilling Equipment  
LDH-80T Drilling Rig, Large Diameter Auger

McLaren/Hart Geologist/Office  
Tim Biggs / St. Louis

Bit Size/Type  
24" OD, Solid Auger

Sample Method  
Grab

T.D. Borehole  
57'

Well Installed?  
None Installed

## Remarks:

Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	None Taken	Background (0.02-0.04)	0.0-48.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, brick, paper, wire, metal, yard waste, and carpeting; soil consisting of olive brown to dark gray silt, gray to black silty clay, and crushed rock; dry to moist, warm.
10	None Taken	Background (0.02-0.04)	
15	None Taken	Background (0.02-0.04)	
20	None Taken	Background (0.02-0.04)	
25	None Taken	Background (0.02-0.04)	
30	None Taken	Background (0.02-0.04)	
35	None Taken	Background (0.02-0.04)	
40	None Taken	Background (0.02-0.04)	
45	None Taken	Background (0.02-0.04)	


# Soil Boring Log



**McLaren  
Hart**

<b>Boring No.</b> WL-109D		<b>Project No./Name</b> 07.0803035.003.002		<b>Page:</b> 1 of 2
<b>Start/Finish Date</b> 10/23/95		<b>Site Name and Location</b> West Lake Landfill; Bridgeton, Missouri		
<b>Drilling Contractor</b> Hart Environmental Drilling		<b>Boring Location:</b> Area 1		
<b>Drilling Service Company</b>		<b>Ground Surface Elevation:</b> 485.6		
<b>Driller</b> Max Timmin		<b>Northing:</b> 1068947.38		
Bruce Murphy		<b>Easting:</b> 516504.97		
		<b>McLaren/Hart Geologist/Office</b> Tim Biggs / St. Louis		
<b>Drilling Equipment</b> CME-55 Drill Rig, Hollow Stem Augers LDH-80T Drill Rig, Large Diameter Auger				
<b>Bit Size/Type</b> 4 1/4" ID & 1/4" Hole 24" OD Solid Auger		<b>Sample Method</b> Continuous Sampler Grab from Auger	<b>T.D. Borehole</b> 59'	<b>Well Installed?</b> D-14
<b>Remarks:</b>				
<b>Depth (ft)</b>	<b>Sample ID #</b>	<b>Gelger Reading (mR/hr)</b>	<b>Description</b>	
5	WL-109D 5'	Background (0.02-0.04)	0.0-56.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, brick, shingles, paper, wire, metal, yard waste, and carpeting; soil consisting of olive brown to dark gray silt, gray to black silty clay, green and red weathered shale, and crushed rock; dry to moist; warm.	
10	WL-109D 10'	Background (0.02-0.04)		
15	WL-109D 15'	Background (0.02-0.04)		
20	WL-109D 20'	Background (0.02-0.04)		
25	WL-109D 25'	Background (0.02-0.04)		
30	WL-109D 30'	Background (0.02-0.04)		
35	WL-109D 35'	None Taken		
40	WL-109D 40'	Background (0.02-0.04)		
45	WL-109D 45'	Background (0.02-0.04)		
50	WL-109D 50'	Background (0.02-0.04)		
55	WL-109D 55'	Background (0.02-0.04)		



Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-109D		Project No./Name 07.0803035.003.002	Page: 2 of 2
Start/Finish Date 10/23/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 1	
Drilling Service Company		Ground Surface Elevation: 485.6	
Driller Max Tinnin		Northing: 1068947.38	
Bruce Murphy		Easting: 516504.97	
		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers LDH-80T Drill Rig, Large Diameter Auger			
Bit Size/Type 4 1/4" ID 8 1/4" Hole 24" OD Solid Auger		Sample Method Continuous Sampler Grab from Auger	T.D. Borehole 59' Well Installed? D-14
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
60	None Taken	Background (0.02-0.04)	56.0-62.0' <u>Native Alluvium</u> : dark gray clayey silt grading to fine-grained sand; moist.
65	None Taken	Background (0.02-0.04)	Auger refusal @ 62.0' (bedrock)

Notes:

Radiological samples not collected during boring activities.  
 Non-radiological samples not collected during boring activities.  
 Perched water not encountered during boring activities.  
 Groundwater not encountered during boring activities.

# Soil Boring Log




**McLaren  
Hart**

Boring No. <b>WL-110</b>		Project No./Name 07.0803035.003.002		Page: 1 of 2
Start/Finish Date 9/6/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri		
Drilling Contractor Drilling Service Company		Boring Location: Area 1 Ground Surface Elevation: 484.41 (Planned Boring)		
Driller Bruce Murphy		Northing: 1068889.01 location, not Easting: 516645.03 surveyed)		
Drilling Equipment LDH-80T Drilling Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis		
Bit Size/Type 24" OD, Solid Auger	Sample Method Grab from Augers	T.D. Borehole 56'	Well Installed? None Installed	


## Remarks:

Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-110 5'	Background (0.02-0.04)	0.0-50.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, wire, insulation, paper, and metal; soil consisting of olive brown silt, dark gray to grayish brown silty clay, and crushed rock; dry to moist; warm to very warm.
10	WL-110 10'	Background (0.02-0.04)	
15	WL-110 15'	Background (0.02-0.04)	
20	WL-110 20'	Background (0.02-0.04)	
25	WL-110 25'	Background (0.02-0.04)	
30	WL-110 30'	Background (0.02-0.04)	
35	WL-110 35'	Background (0.02-0.04)	
40	WL-110 40'	Background (0.02-0.04)	
45	WL-110 45'	Background (0.02-0.04)	
50	WL-110 50'	Background (0.02-0.04)	

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-110		Project No./Name 07.0803035.003.002	Page: 2 of 2
Start/Finish Date 9/6/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 1 Ground Surface Elevation: 484.41 (Planned Boring)	
Driller Bruce Murphy		Northing: 1068889.01 (location, not surveyed) Easting: 516645.03 (surveyed)	
Drilling Equipment LDH-80T Drilling Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD, Solid Auger	Sample Method Grab from Augers	T.D. Borehole 56'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geliger Reading (mR/hr)	Description
55	WL-110 55'	Background (0.02-0.04)	50.0-56.0' <u>Native Alluvium</u> : dark gray, clayey silt; moist; very warm.
60	WL-110 56'	Background (0.02-0.04)	@ 56.0' sample had a temperature of 140° F Boring terminated at 56.0'


Notes:

Radiological samples collected from 5 and 50 feet below ground surface.  
 Non-radiological samples not collected during boring activities.  
 Perched water not encountered during boring activities.  
 Groundwater not encountered during boring activities.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-111		Project No./Name 07.0803035:003.002	Page: 1 of 1
Start/Finish Date 9/11/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 1	
Driller Bruce Murphy		Ground Surface Elevation: 474.5	
		Northing: 1069187.35	
		Easting: 516583.61	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 52'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (in R/hr)	Description
5	WL-111 5'	Background (0.02-0.04)	0.0-50.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, cloth, brick, rubber, paper, wire, glass, and metal; soil consisting of olive brown to gray silt, dark gray to grayish brown silty clay, and crushed rock; dry to wet.
10	WL-111 10'	Background (0.02-0.04)	
15	WL-111 15'	Background (0.02-0.04)	
20	WL-111 20'	Background (0.02-0.04)	
25	WL-111 25'	Background (0.02-0.04)	
30	WL-111 30'	Background (0.02-0.04)	
35	WL-111 35'	Background (0.02-0.04)	
40	WL-111 40'	Background (0.02-0.04)	
45	WL-111 45'	Background (0.02-0.04)	
50	WL-111 50'	Background (0.02-0.04)	
55	WL-111 51'	Background (0.02-0.04)	50.0-52.0' <u>Native Alluvium</u> : dark gray, silty, very fine-grained sand; wet. Boring terminated @ 52.0'.  @ 45' wet


**Notes:**

- Radiological samples collected at 5 and 51 feet below ground surface.
- Non-radiological samples not collected during boring activities.
- Perched water not encountered during boring activities.
- Groundwater encountered at 45 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-112		Project No./Name 07.0803035.003.002	
Start/Finish Date 9/11/95		Page: 1 of 1	
Site Name and Location West Lake Landfill; Bridgeton, Missouri			
Drilling Contractor Drilling Service Company		Boring Location: Area 1	
Driller Bruce Murphy		Ground Surface Elevation: 467.6	
		Northing: 1069379.45	
		Easting: 516628.22	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 42'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-112 5'	Background (0.02-0.04)	0.0-38.0' <u>Landfill Debris</u> : trashy debris consisting of yard waste, wood, plastic, cloth, paper, wire, and metal; soil consisting of grayish brown to dark gray silt, dark gray to grayish brown clayey silt, and very fine-grained sand; dry to wet.
10	None Taken	None Taken	
15	WL-112 15'	Background (0.02-0.04)	
20	WL-112 20'	Background (0.02-0.04)	
25	WL-112 25'	Background (0.02-0.04)	
30	WL-112 30'	Background (0.02-0.04)	
35	WL-112 35'	Background (0.02-0.04)	@ 34' wet
40	None Taken	None Taken	38.0-42.0' <u>Native Alluvium</u> : dark gray silty clay grading to very fine-grained sand; moist to wet.
45	None Taken	None Taken	Boring terminated @ 42.0'

Notes:

Radiological samples collected at 5 and 42 feet below ground surface.  
 Non-radiological samples not collected during boring activities.  
 Perched water not encountered during boring activities.  
 Groundwater encountered at 34 feet below ground surface.

Soil Boring Log				McLaren Hart	
Boring No. WL-113		Project No./Name 07.0803035.003.002		Page: 1 of 1	
Start/Finish Date 9/25/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri			
Drilling Contractor Drilling Service Company		Boring Location: Area 1			
Driller Bruce Murphy		Ground Surface Elevation: 467			
		Northing: 1069483.19			
		Easting: 516469.95			
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger			McLaren/Hart Geologist/Office Tim Biggs / St. Louis		
Bit Size/Type 24" OD Solid Auger		Sample Method Grab from Auger		T.D. Borehole 45'	Well Installed? None Installed
Remarks:					
Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description		
5	WL-113 5'	Background (0.01-0.04)	0.0-42.5' <u>Landfill Debris</u> : trashy debris consisting of yard waste, wood, plastic, cloth, paper, wire, and metal; soil consisting of dark gray to grayish brown silty clay and very fine to medium-grained sand; dry to wet.		
10	WL-113 10'	Background (0.01-0.04)			
15	WL-113 15'	Background (0.01-0.04)			
20	WL-113 20'	Background (0.01-0.04)			
25	None Taken	Background (0.01-0.04)			
30	None Taken	Background (0.01-0.04)			
35	WL-113 35'	Background (0.01-0.04)			
40	None Taken	Background (0.01-0.04)	@ 41' wet		
45	None Taken	Background (0.01-0.04)			
			42.5-45.0' <u>Native Alluvium</u> : dark gray silty clay grading to very fine-grained sand; wet. Boring terminated @ 45.0'.		


Notes:

Radiological samples collected at 5 and 10 feet below ground surface; duplicate collected and analyzed for 5' sample; downhole logging indicated elevated gamma readings from 3.5 -4.0'.

Non-radiological samples collected at 45 feet below ground surface; priority pollutant sample collected and analyzed.

Perched water not encountered during boring activities.

Groundwater encountered at 41 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-114		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/25/95		Site Name and Location West Lake Landfill: Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 1 Ground Surface Elevation: 468.3	
Driller Bruce Murphy		Northing: 1069391.53 Easting: 516338.57	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 45'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-114 5'	Background (0.01-0.05)	0.0-40.0' <u>Landfill Debris</u> : trashy debris consisting of yard waste, wood, plastic, cloth, paper, insulation, wire, and metal; soil consisting of dark gray to grayish brown clayey silt and very fine to medium-grained sand; dry to moist.
10	None Taken	Background (0.01-0.05)	
15	WL-114 15'	Background (0.01-0.05)	
20	WL-114 20'	Background (0.01-0.05)	
25	WL-114 25'	Background (0.01-0.05)	
30	WL-114 30'	Background (0.01-0.05)	
35	WL-114 35'	Background (0.01-0.05)	
40	WL-114 40'	Background (0.01-0.05)	40.0-45.0' <u>Native Alluvium</u> : dark gray, silty, fine to medium-grained sand; wet. Boring terminated @ 45.0'.
45	None Taken	Background (0.01-0.05)	


Notes:

Radiological samples collected at 5 and 15 feet below ground surface; downhole logging indicated elevated gamma readings from 4.0-5.0'.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater encountered at 41 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-115		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/26/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor		Boring Location: Area 1	
Drilling Service Company		Ground Surface Elevation: 468.9	
Driller Bruce Murphy		Northing: 1069298.98 Easting: 516395.13	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 41'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-115 5'	Background (0.01-0.04)	0.0-34.0' <u>Landfill Debris</u> : trashy debris consisting of yard waste, rubber, wood, plastic, cloth, paper, insulation, wire, and metal; soil consisting of dark gray to grayish brown clayey silt and silty sand; dry to moist.
10	WL-115 10'	Background (0.01-0.04)	
15	WL-115 15'	Background (0.01-0.04)	
20	None Taken	Background (0.01-0.04)	
25	WL-115 25'	Background (0.01-0.04)	
30	None Taken	Background (0.01-0.04)	
35	WL-115 35'	Background (0.01-0.04)	34.0-41.0' <u>Native Alluvium</u> : dark gray, silty, fine to medium-grained sand; moist to wet.  @ 40' wet
40	WL-115 40'	Background (0.01-0.04)	
45	None Taken	None Taken	
Boring terminated @ 41.0'			

Notes:


Radiological samples collected at 5 and 40 feet below ground surface.

Non-radiological samples collected at 5 and 38 feet below ground surface; contingency sampling.

Perched water not encountered during boring activities.

Groundwater encountered at 40 feet below ground surface.



Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-116		Project No./Name 07.0803035.003.002	
Start/Finish Date 9/26/95		Page: 1 of 1	
Site Name and Location West Lake Landfill; Bridgeton, Missouri		Boring Location: Area 1	
Drilling Contractor Drilling Service Company		Ground Surface Elevation: 474.3	
Driller Bruce Murphy		Northing: 1069083.49 Easting: 516160.60	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 20'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description
5	WL-116 5'	Background (0.01-0.04)	0.0-20.0' <u>Landfill Debris</u> : trashy debris consisting of yard waste, wood, plastic, cloth, paper, and metal; soil consisting of dark gray silty clay; dry to wet.  @ 8' wet
10	WL-116 10'	Background (0.01-0.04)	
15	None Taken	Background (0.01-0.04)	
20	None Taken	None Taken	Boring abandoned @ 20.0'


Notes:

Radiological samples collected at 5 and 10 feet below ground surface; duplicate collected and analyzed for 5' sample.

Non-radiological samples not collected during boring activities.

Perched water encountered at 8 feet below ground surface.

Groundwater not encountered during boring activities.

Soil Boring Log			
Boring No. WL-117		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/27/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 1	
Driller Bruce Murphy		Ground Surface Elevation: 467.6	
		Northing: 1069237.40	
		Easting: 516221.33	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 41'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description
5	WL-117 5'	Background (0.01-0.04)	0.0-37.0' <u>Landfill Debris</u> : trashy debris consisting of yard waste, wood, wire, insulation, plastic, cloth, paper, and metal; soil consisting of dark gray silty clay; dry to wet.
10	WL-117 10'	Background (0.01-0.04)	
15	WL-117 15'	Background (0.01-0.04)	
20	None Taken	Background (0.01-0.04)	
25	WL-117 25'	Background (0.01-0.04)	
30	WL-117 30'	Background (0.01-0.04)	
35	WL-117 35'	Background (0.01-0.04)	37.0-41.0' <u>Native Alluvium</u> : dark gray, silty, fine to medium-grained sand; moist to wet.  @ 40' wet Boring terminated @ 41.0'
40	WL-117 40'	Background (0.01-0.04)	
45	None Taken	None Taken	


Notes:

Radiological samples collected at 10 and 25 feet below ground surface; downhole logging indicated elevated gamma readings from 6.0-7.0'.

Non-radiological samples not collected during boring activities.


Perched water not encountered during boring activities.

Groundwater encountered at 40 feet below ground surface.

Soil Boring Log		 <b>McLaren/Hart</b>	
Boring No. WL-118		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/28/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor		Boring Location: Area 1	
Drilling Service Company		Ground Surface Elevation: 465.8	
Driller		Northing: 1069411.09	
Bruce Murphy		Easting: 516304.95	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 15'	Well Installed? None Installed
Remarks:			
Depth (m)	Sample ID #	Geiger Reading (mR/hr)	Description
5	WL-118 5'	Background (0.01-0.04)	0.0-15.0' <u>Landfill Debris</u> : trashy debris consisting of plastic, cloth, paper, glass, and metal; soil consisting of light brown to dark gray, silty, plastic clay; dry to moist.  Boring terminated @ 15.0'
10	WL-118 10'	Background (0.01-0.04)	
15	WL-118 15'	Background (0.01-0.04)	

Notes:

Radiological samples collected at 5 and 10 feet below ground surface.  
 Non-radiological samples not collected during boring activities.  
 Perched water not encountered during boring activities.  
 Groundwater not encountered during boring activities.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-119		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/29/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 1	
Driller Bruce Murphy		Ground Surface Elevation: 477.4	
		Northing: 1069031.14	
		Easting: 516289.26	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 50'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-119 5'	Background (0.01-0.04)	0.0-44.0' <u>Landfill Debris</u> : trashy debris consisting of yard waste, insulation, wire, wood, plastic, shingles, cloth, carpet, paper, glass, and metal; soil consisting of light brown to dark gray, silty, plastic clay to sandy silt; dry to moist.
10	None Taken	Background (0.01-0.04)	
15	WL-119 15'	Background (0.01-0.04)	
20	None Taken	Background (0.01-0.04)	
25	WL-119 25'	Background (0.01-0.04)	
30	None Taken	Background (0.01-0.04)	
35	None Taken	Background (0.01-0.04)	
40	None Taken	Background (0.01-0.04)	44.0-50.0' <u>Native Alluvium</u> : dark gray, silty, fine to medium-grained sand; moist.
45	WL-119 45'	Background (0.01-0.04)	
50	WL-119 50'	Background (0.01-0.04)	
Boring terminated @ 50.0'			

Notes:

Radiological samples collected at 5 and 50 feet below ground surface; duplicate collected and analyzed for 50' sample.

Non-radiological samples collected at 50 feet below ground surface; priority pollutant and priority pollutant duplicate sample collected and analyzed.

Perched water not encountered during boring activities.

Groundwater not encountered during boring activities.

# Soil Boring Log



**McLaren  
Hart**

Boring No. WL-120		Project No./Name 07.0803035.003.002		Page: 1 of 1
Start/Finish Date 9/29/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri		
Drilling Contractor Drilling Service Company		Boring Location: Area 1		
Driller Bruce Murphy		Ground Surface Elevation: 474.7		
		Northing: 1069053.64		
		Easting: 516846.57		
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis		
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 52'	Well Installed? None Installed	
Remarks:				
Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description	
5	WL-120 5'	Background (0.01-0.04)	0.0-52.0' <u>Landfill Debris</u> : trashy debris consisting of yard waste, insulation, rubber, wire, wood, plastic, shingles, cloth, carpet, paper, glass, and metal; soil consisting of light brown to dark gray, silty, plastic clay to silty sand; dry to wet.	
10	None Taken	Background (0.01-0.04)		
15	None Taken	Background (0.01-0.04)		
20	WL-120 20'	Background (0.01-0.04)		
25	WL-120 25'	Background (0.01-0.04)		
30	None Taken	Background (0.01-0.04)		
35	None Taken	Background (0.01-0.04)		
40	None Taken	Background (0.01-0.04)		
45	None Taken	Background (0.01-0.04)		
50	WL-120 50'	Background (0.01-0.04)		
55	None Taken	Background (0.01-0.04)	Boring terminated @ 52.0'	

## Notes:

Radiological samples collected at 5 and 50 feet below ground surface; duplicate collected and analyzed for 50' sample.

Non-radiological samples not collected during boring activities.


Perched water not encountered during boring activities.

Groundwater not encountered during boring activities.

---

## Area 2 Boring Logs

---

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-201		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 7/31/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 2 Ground Surface Elevation: 444	
Driller Max Tinnin		Northing: 1070378.84 Easting: 514177.60	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5' Continuous Sampler	T.D. Borehole 15'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-201 5'	Background (0.05-0.07)	0.0-15.0' <u>Native Alluvium</u> : olive brown silt and alternating layers of very fine-grained sand and slightly clayey silt grading to fine to medium-grained sand; dry to wet @ 8' wet
10	WL-201 10'	Background (0.05-0.07)	
15	WL-201 15'	Background (0.05-0.07)	
Boring terminated @ 15.0'			


Notes:

Radiological samples collected at 5 and 15 feet below ground surface.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater encountered at 8 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-202		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 7/31/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 2	
Driller Max Tinnin		Ground Surface Elevation: 444.9	
		Northing: 1070102.59	
		Easting: 514488.27	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5' Continuous Sampler	T.D. Borehole 15'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geliger Reading (mR/hr)	Description
5	WL-202 5'	Background (0.05-0.07)	0.0-15.0' <u>Native Alluvium</u> : light to dark brown silt grading to fine grained sand; dry to wet  @ 10' wet  Boring terminated @ 15.0'
10	WL-202 10'	Background (0.05-0.07)	
15	WL-202 15'	Background (0.05-0.07)	

Notes:


Radiological samples collected at 5 and 15 feet below ground surface.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.


Groundwater encountered at 10 feet below ground surface.



Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-203		Project No./Name 07.0803035.003.002	
Start/Finish Date 7/31/95		Page: 1 of 1	
Site Name and Location West Lake Landfill; Bridgeton, Missouri			
Boring Location: Area 2			
Ground Surface Elevation: 444.7			
Northing: 1069934.54			
Easting: 514237.48			
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5' Continuous Sampler	T.D. Borehole 15'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mL/hr)	Description
5	WL-203 5'	Background (0.05-0.07)	0.0-15.0' <u>Native Alluvium</u> : dark brown to silt grading to light brown, fine-grained sand; dry to wet.  @ 11' wet  Boring terminated @ 15.0'
10	WL-203 10'	Background (0.05-0.07)	
15	WL-203 15'	Background (0.05-0.07)	

Notes:

Radiological samples collected at 5 and 15 feet below ground surface.  
 Non-radiological samples not collected during boring activities.  
 Perched water not encountered during boring activities.  
 Groundwater encountered at 11 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-204		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/1/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 2	
		Ground Surface Elevation: 443.3	
Driller Max Tinnin		Northing: 1069685.83	
		Easting: 514205.01	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5' Continuous Sampler	T.D. Borehole 25'	Well Installed? S-1
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-204 5'	Background (0.03-0.05)	0.0-25.0' <u>Native Alluvium</u> : olive brown clayey silt grading to dark brown, fine-grained sand; moist to wet.  @ 8' wet    Boring terminated @ 25.0'
10	WL-204 10'	Background (0.03-0.05)	
15	WL-204 15'	Background (0.03-0.05)	
20	WL-204 20'	Background (0.03-0.05)	
25	WL-204 25'	Background (0.03-0.05)	

Notes:

Radiological samples collected at 5 and 25 feet below ground surface.  
 Non-radiological samples not collected during boring activities.  
 Perched water not encountered during boring activities.  
 Groundwater encountered at 8 feet below ground surface.

# Soil Boring Log



**McLaren  
Hart**

Boring No. <b>WL-205</b>		Project No./Name 07.0803035.003.002		Page: 1 of 1
Start/Finish Date 8/1/95 / 8/3/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri		
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 2		
Driller Max Tinnin		Ground Surface Elevation: 443.2		
		Northing: 1069698.26		
		Easting: 514212.18		
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis		
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5' Continuous Sampler	T.D. Borehole 52'	Well Installed? I-2	

Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-205 5'	Background (0.05-0.07)	0.0-52.0' <u>Native Alluvium</u> : olive brown silty clay grading to grayish brown, coarse-grained sand with gravel; dry to wet.  @ 8' wet
10	WL-205 10'	Background (0.05-0.07)	
15	WL-205 15'	Background (0.05-0.07)	
20	WL-205 20'	Background (0.05-0.07)	
25	WL-205 25'	Background (0.05-0.07)	
30	None Taken	Background (0.05-0.07)	
35	WL-205 32'	Background (0.05-0.07)	
40	WL-205 37'	Background (0.05-0.07)	
45	WL-205 42'	Background (0.05-0.07)	
50	WL-205 47'	Background (0.05-0.07)	
55	WL-205 52'	Background (0.05-0.07)	Boring terminated @ 52.0'

## Notes:

Radiological samples collected at 5 and 15 feet below ground surface.

Non-radiological samples not collected.

Perched water not encountered during boring activities.

Groundwater encountered at 8 feet below ground surface.


# Soil Boring Log



**McLaren  
Hart**


Boring No. WL-206		Project No./Name 07.0803035.003.002		Page: 1 of 2
Start/Finish Date 8/16/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri		
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 2		
		Ground Surface Elevation: 444.4		
Driller Max Tinnin		Northing: 1070194.31		
		Easting: 514549.50		
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis		
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5" Continuous Sampler	T.D. Borehole 109'	Well Installed? D-6	

Remarks:			
Depth (ft)	Sample ID #	Geliger Reading (mR/hr)	Description
5	WL-206 5'	Background (0.02-0.04)	0.0-65.0' <u>Native Alluvium</u> : olive brown clayey silt grading to grayish brown, coarse-grained sand and gravel; dry to wet.  @ 11' wet
10	WL-206 10'	Background (0.02-0.04)	
15	WL-206 15'	Background (0.02-0.04)	
20	None Taken	None Taken	
25	None Taken	None Taken	
30	None Taken	None Taken	
35	None Taken	None Taken	
40	None Taken	None Taken	
45	None Taken	None Taken	
50	None Taken	None Taken	
55	None Taken	None Taken	
60	None Taken	None Taken	
65	None Taken	None Taken	

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-206		Project No./Name 07.0803035.003.002	Page: 2 of 2
Start/Finish Date 8/16/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 2	
		Ground Surface Elevation: 444.4	
Driller Max Tinnin		Northing: 1070194.31	
		Easting: 514549.50	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5' Continuous Sampler	T.D. Borehole 109'	Well Installed? D-6
Remarks:			
Depth (ft)	Sample ID #	Geliger Reading (min/hr)	Description
70	None Taken	None Taken	65.0-109.0' <u>Native Alluvium</u> : olive brown clayey silt grading to grayish brown, coarse-grained sand and gravel; dry to wet.
75	None Taken	None Taken	
80	None Taken	None Taken	
85	None Taken	None Taken	
90	None Taken	None Taken	
95	None Taken	None Taken	
100	None Taken	None Taken	
105	None Taken	None Taken	
110	None Taken	None Taken	Auger refusal @ 109.0' (bedrock)

Notes:

Radiological samples collected at 5 and 10 feet below ground surface.  
 Non-radiological samples not collected during boring activities.  
 Perched water not encountered during boring activities.  
 Groundwater encountered at 11 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-207		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/18/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 2	
Driller Max Tinnin		Ground Surface Elevation: 444.5	
		Northing: 1070743.05	
		Easting: 514299.87	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5' Continuous Sampler	T.D. Borehole 50'	Well Installed? I-7
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mN/hr)	Description
5	WL-207 5'	Background (0.02-0.04)	0.0-50.0' <u>Native Alluvium</u> : slightly clayey, very fine-grained sand grading to gray coarse-grained sand with gravel; dry to wet  @ 9.5' wet
10	WL-207 10'	Background (0.02-0.04)	
15	WL-207 15'	Background (0.02-0.04)	
20	WL-207 20'	Background (0.02-0.04)	
25	WL-207 25'	None Taken	
30	WL-207 30'	None Taken	
35	WL-207 35'	None Taken	
40	WL-207 40'	None Taken	
45	WL-207 45'	None Taken	
50	WL-207 50'	None Taken	


Notes:

Radiological samples collected at 5 and 10 feet below ground surface.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater encountered at 9.5 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-208		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/23/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor		Boring Location: Area 2	
Drilling Service Company		Ground Surface Elevation: 474.8	
Driller		Northing: 1070141.19	
Bruce Murphy		Easting: 514752.42	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 37'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-208 5'	Background (0.03-0.05)	0.0-28.0' <u>Landfill Debris</u> : trashy debris consisting of wood, brick, paper, concrete, insulation, metal, plastic, glass, and wire; soil consisting of dark gray silty clay to medium-grained sand, and rock; dry to moist.  @ 15' soil discolored; petroleum odor; OVM readings greater than 10 X background.  @ 20' metal container with petroleum odor and residue; OVM readings greater than 10 X background.  @ 25' OVM readings greater than 10 X background.
10	WL-208 10'	Background (0.03-0.05)	
15	WL-208 15'	Background (0.03-0.05)	
20	WL-208 20'	Background (0.03-0.05)	
25	WL-208 25'	Background (0.03-0.05)	
30	WL-208 30'	Background (0.03-0.05)	28.0-37.0' <u>Native Alluvium</u> : dark gray, slightly sandy, silty plastic clay grading to fine-grained sand; moist
35	WL-208 35'	Background (0.03-0.05)	
40	WL-208 37'	Background (0.03-0.05)	


Notes:

Radiological samples collected at 5 and 9 feet below ground surface.

Non-radiological samples collected at 15, 20 and 28 feet below ground surface; contingency sampling.

Perched water not encountered during boring activities.

Groundwater not encountered during boring activities.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-209		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/24/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor		Boring Location: Area 2	
Drilling Service Company		Ground Surface Elevation: 467.4	
Driller Bruce Murphy		Northing: 1070492.55	
		Easting: 514686.34	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 30'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-209 5'	1.0-5.3	0.0-28.0' <u>Landfill Debris</u> : trashy debris consisting of rubber, brick, concrete, insulation, metal, wood, plastic, glass, and wire; soil consisting of dark gray clayey silt to fine-grained sand, and rock; dry to moist.
10	WL-209 10'	0.8-1.3	
15	WL-209 15'	Background (0.05)	
20	WL-209 20'	Background (0.05)	
25	WL-209 25'	Background (0.05)	
30	WL-209 30'	Background (0.05)	28.0-30.0' <u>Native Alluvium</u> : dark gray, fine to medium-grained sand; moist. Boring terminated @ 30.0'

Notes:


Radiological samples collected at 5 and 25 feet below ground surface; duplicates collected and analyzed; downhole logging indicated elevated gamma levels from 0.0-7.0'.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater not encountered during boring activities.



Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-210		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/25/95 / 8/28/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor		Boring Location: Area 2	
Drilling Service Company		Ground Surface Elevation: 477.8	
Driller Bruce Murphy		Northing: 1069775.15 Easting: 514811.55	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 53'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geliger Reading (uR/hr)	Description
5	WL-210 5'	0.2-3.0	0.0-53.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, paper, shredded tires, yard waste, cloth, metal, glass, and wire; soil consisting of dark gray to brown silt and fine-grained sand, and crushed rock; dry to wet.  0-46' OVM readings greater than 10X background.  @ 15' soil discolored; petroleum odor; OVM readings greater than 10 X background.
10	None Taken	Background (0.2)	
15	WL-210 15'	Background (0.2)	
20	WL-210 20'	Background (0.2)	
25	WL-210 25'	Background (0.2)	
30	WL-210 30'	Background (0.2)	
35	WL-210 35'	Background (0.2)	
40	WL-210 40'	Background (0.2)	
45	None Taken	None Taken	
50	None Taken	None Taken	
55	None Taken	None Taken	53.0' Native Alluvium: dark gray, slightly sandy, silty, plastic clay; wet. Boring terminated @ 53.0'


Notes:

Radiological samples collected at 5 and 40 feet below ground surface; duplicates collected and analyzed; downhole logging indicated elevated gamma readings from 0.0-13.0'.

Non-radiological samples collected at 15 feet below ground surface; contingency sampling.

Perched water not encountered during boring activities.

Groundwater encountered at 46 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-211		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/28/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor		Boring Location: Area 2	
Drilling Service Company		Ground Surface Elevation: 475.3	
Driller Bruce Murphy		Northing: 1070046.08	
		Easting: 514684.07	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 28'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-211 5'	Background (0.4)	0.0-25.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, paper, rubber, metal, and concrete; soil consisting of grayish-brown sandy and silty clay to coarse-grained sand; dry to wet.  @ 5-20' OVM readings greater than 10 X background  @ 23.5' wet
10	WL-211 10'	Background (0.4)	
15	WL-211 15'	Background (0.4)	
20	WL-211 20'	Background (0.4)	
25	WL-211 25'	Background (0.4)	
30	WL-211 30'	Background (0.4)	25.0-28.0' <u>Native Alluvium</u> : grayish brown, fine to coarse-grained sand; wet. Boring terminated @ 28.0'

Notes:


Radiological samples collected at 5 and 25 feet below ground surface; downhole logging

indicated elevated gamma readings from 0.0-7.5' and 9.0-10.0'.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater encountered at 23.5 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-212		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/28/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 2	
Driller Bruce Murphy		Ground Surface Elevation: 472.9	
		Northing: 1070025.86	
		Easting: 514973.26	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 30'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geliger Reading (nR/hr)	Description
5	WL-212 5'	Background (0.03-0.05)	0.0-28.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, brick, paper, rubber, insulation; soil consisting of dark gray silty clay, silt, and very fine-grained sand, and crushed rock; dry to moist.
10	WL-212 10'	Background (0.03-0.05)	
15	WL-212 15'	Background (0.03-0.05)	
20	WL-212 20'	Background (0.03-0.05)	
25	None Taken	Background (0.03-0.05)	
30	WL-212 28'	Background (0.03-0.05)	28.0-30.0' <u>Native Alluvium</u> : dark gray silt grading to very fine grained sand; moist. Boring terminated @ 30.0'


Notes:

Radiological samples collected at 5 and 10 feet below ground surface.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater not encountered during boring activities.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-213		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/29/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor		Boring Location:	Area 2
Drilling Service Company		Ground Surface Elevation:	472.3
Driller Bruce Murphy		Northing:	1070223.38
		Easting:	514947.61
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 25'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geiger Reading (uR/hr)	Description
5	WL-213 5'	Background (0.02-0.04)	0.0-24.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, brick, cardboard, paper, wire, rubber, metal; soil consisting of dark gray silty clay and black, sandy, clayey silt to dark gray, silty very fine-grained sand and crushed rock; dry to moist.
10	WL-213 10'	Background (0.02-0.04)	
15	WL-213 15'	Background (0.02-0.04)	
20	None Taken	None Taken	
25	WL-213 25'	Background (0.02-0.04)	24.0-25.0' Native Alluvium: dark gray, silty, very fine-grained sand; moist. Boring terminated @ 25.0'


Notes:

Radiological samples collected at 5 and 25 feet below ground surface.

Non-radiological samples collected at 25 feet below ground surface; priority pollutant sampling.

Perched water not encountered during boring activities.

Groundwater not encountered during boring activities.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-214		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/29/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor		Boring Location: Area 2	
Drilling Service Company		Ground Surface Elevation: 468.5	
Driller Bruce Murphy		Northing: 1070206.86	
		Easting: 515241.19	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 25'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geliger Reading (mL/hr)	Description
5	WL-214 5'	Background (0.02-0.04)	0.0-24.0' <u>Landfill Debris</u> : trashy debris consisting of shingles, carpeting, glass, wood, plastic, brick, paper, wire, and metal; soil consisting of dark gray clayey silt to fine-grained sand; dry to moist.
10	WL-214 10'	Background (0.02-0.04)	
15	WL-214 15'	Background (0.02-0.04)	
20	WL-214 20'	Background (0.02-0.04)	
25	WL-214 25'	Background (0.02-0.04)	24.0-25.0' <u>Native Alluvium</u> : dark gray, silty, fine-grained sand; moist. Boring terminated @ 25.0'


Notes:

Radiological samples collected at 5 and 25 feet below ground surface.

Non-radiological samples collected at 25 feet below ground surface; priority pollutant sampling.

Perched water not encountered during boring activities.

Groundwater not encountered during boring activities.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-215		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/29/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 2	
Driller Bruce Murphy		Ground Surface Elevation: 470	
		Northing: 1070432.01	
		Easting: 515259.72	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 16'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-215 5'	Background (0.02-0.04)	0.0-16.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, rubber, and wire; soil consisting of dark gray to black silty clay; dry to wet. @ 6' wet  Boring abandoned @ 16.0'
10	None Taken	None Taken	
15	None Taken	None Taken	
20	None Taken	None Taken	

**Notes:**

- Radiological samples not collected during boring activities.
- Non-radiological samples not collected during boring activities.
- Perched water encountered at 6 feet below ground surface.
- Groundwater not encountered during boring activities.

# Soil Boring Log



**McLaren  
Hart**

Boring No.  
WL-216A

Project No./Name  
07.0803035.003.002

Page:  
1 of 3

**Start/Finish Date**

8/29/95 / 10/17/95

**Site Name and Location**

West Lake Landfill; Bridgeton, Missouri

**Drilling Contractor**

Hart Environmental Drilling

Drilling Service Company

**Boring Location:**

Area 2

**Ground Surface Elevation:**

477.4

**Northing:**

1069836.29

**Driller**

Max Tinnin

Bruce Murphy

**Easting:**

514936.08

McLaren/Hart Geologist/Office

Tim Biggs / St. Louis

**Drilling Equipment**

CME-55 Drill Rig, Hollow Stem Augers

LDH-80T Drill Rig, Large Diameter Auger

**Bit Size/Type**

4 1/8" Drag Bit (mud rotary)

4 1/4" ID; 8 1/4" Hole

24" OD Solid Auger

**Sample Method**

5' Continuous Sampler

Grab from Auger

**T.D. Borehole**

146.2

**Well Installed?**

D-12

Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description
<b>Remarks:</b>			
5	WL-216 5'	Background	0.0-22.0' <u>Landfill Debris</u> : soil consisting of grayish brown to olive brown silty clay to gray, very fine-grained sand, and crushed rock; no trashy debris encountered; dry to moist.
10	WL-216 10'	Background	
15	WL-216 15'	Background	
20	WL-216 20'	Background	
25	WL-216 25'	Background	22.0-65.0' <u>Native Alluvium</u> : gray, silty, very fine-grained sand grading to coarse-grained sand, gravel, cobbles, and coal; moist to wet.
30	None Taken	None Taken	
35	None Taken	None Taken	
40	None Taken	None Taken	
45	None Taken	None Taken	@ 48" wet
50	None Taken	None Taken	
55	None Taken	None Taken	
60	None Taken	None Taken	

# Soil Boring Log



**McLaren  
Hart**

Boring No.  
WL-216A

Project No./Name  
07.0803035.003.002

Page:  
2 of 3

Start/Finish Date  
8/29/95 / 10/17/95

Site Name and Location  
West Lake Landfill; Bridgeton, Missouri

Drilling Contractor  
Hart Environmental Drilling  
Drilling Service Company

Boring Location: Area 2  
Ground Surface Elevation: 477.4  
Northing: 1069836.29  
Easting: 514936.08

Driller  
Max Tinnin  
Bruce Murphy

McLaren/Hart Geologist/Office  
Tim Biggs / St. Louis

Drilling Equipment  
CME-55 Drill Rig, Hollow Stem Augers  
LDH-80T Drill Rig, Large Diameter Auger

Bit Size/Type  
4 1/8" Drag Bit (mud rotary)  
4 1/4" ID; 8 1/4" Hole  
24" OD Solid Auger

Sample Method  
5" Continuous Sampler  
Grab from Auger


T.D. Borehole  
146.2

Well Installed?  
D-12

## Remarks:

Depth (ft)	Sample ID #	Gelger Reading (unit/hr)	Description
65	None Taken	None Taken	65.0-125.0' Native Alluvium: gray, silty, very fine-grained sand grading to coarse-grained sand, gravel, cobbles, and coal; moist to wet.
70	None Taken	None Taken	
75	None Taken	None Taken	
80	None Taken	None Taken	
85	None Taken	None Taken	
90	None Taken	None Taken	
95	None Taken	None Taken	
100	None Taken	None Taken	
105	None Taken	None Taken	
110	None Taken	None Taken	
115	None Taken	None Taken	



Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-216A		Project No./Name 07.0803035.003.002	Page: 3 of 3
Start/Finish Date 8/29/95 / 10/17/95		Site Name and Location West Lake Landfill, Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 2	
Drilling Service Company		Ground Surface Elevation: 477.4	
Driller Max Timmin Bruce Murphy		Northing: 1069836.29 Easting: 514936.08	
		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers LDH-80T Drill Rig, Large Diameter Auger			
Bit Size/Type 4 1/8" Drag Bit (mud rotary) 4 1/4" ID; 8 1/4" Hole 24" OD Solid Auger	Sample Method 5' Continuous Sampler Grab from Auger	T.D. Borehole 146.2	Well Installed? D-12
Remarks:			
Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description
120	None Taken	None Taken	125.0-146.2' <u>Native Alluvium</u> : gray, silty, very fine-grained sand grading to coarse-grained sand, gravel, cobbles, and coal; moist to wet.
125	None Taken	None Taken	
130	None Taken	None Taken	
135	None Taken	None Taken	
140	None Taken	None Taken	
145	None Taken	None Taken	
150	None Taken	None Taken	Auger refusal @ 146.2' (bedrock)

Notes:

Radiological samples collected at 5 and 25 feet below ground surface; downhole logging indicated elevated gamma readings from 2.5-5.0'.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater encountered at 48 feet below ground surface.

# Soil Boring Log



**McLaren  
Hart**

Boring No. <b>WL-216B (WL-232)</b>		Project No./Name 07.0803035.003.002		Page: 1 of 1
Start/Finish Date 8/30/95 / 9/19/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri		
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 1		
Drilling Service Company		Ground Surface Elevation: 477.5		
Driller Max Tinnin		Northing: 1069827.87		
Bruce Murphy		Easting: 514931.35		
McLaren/Hart Geologist/Office Tim Biggs / St. Louis				
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers LDH-80T Drill Rig, Large Diameter Auger				
Bit Size/Type 4 1/4" ID; 8 1/4" Hole 24" OD Solid Auger		Sample Method 5' Continuous Sampler Grab from Auger	T.D. Borehole 54.5'	Well Installed? S-10
Remarks:				
Depth (ft)	Sample ID #	Gelger Reading (mL/hr)	Description	
5	None Taken	Background (0.01-0.03)	0.0-22.0' <u>Landfill Debris</u> : soil consisting of grayish brown to olive brown silty clay to gray, very-fine grained sand, and crushed rock; no trashy debris encountered; dry to moist.	
10	None Taken	Background (0.01-0.03)		
15	None Taken	Background (0.01-0.03)		
20	None Taken	Background (0.01-0.03)		
25	None Taken	None Taken	22.0-54.5' <u>Native Alluvium</u> : gray, silty, very fine-grained sand grading to coarse-grained sand; moist to wet.  @ 40' wet	
30	None Taken	None Taken		
35	None Taken	None Taken		
40	None Taken	None Taken		
45	None Taken	None Taken		
50	None Taken	None Taken		
55	None Taken	None Taken		
			Boring terminated @ 54.5'	

## Notes:


- Radiological samples not collected during boring activities; downhole logging indicated elevated gamma readings from 3.0-5.0'.
- Non-radiological samples not collected during boring activities.
- Perched water not encountered during boring activities.
- Groundwater encountered at 40 feet below ground surface.

# Soil Boring Log



**McLaren  
Hart**

Boring No. WL-216C		Project No./Name 07.0803035.003.002		Page: 1 of 2
Start/Finish Date 8/30/95 / 10/13/95		Site Name and Location West Lake Landfill: Bridgeton, Missouri		
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 2		
Drilling Service Company		Ground Surface Elevation: 477.6		
Driller Max Tinnin		Northing: 1069819.16		
Bruce Murphy		Easting: 514925.06		
McLaren/Hart Geologist/Office Tim Biggs / St. Louis				
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers LDH-80T Drill Rig, Large Diameter Auger				
Bit Size/Type 4 1/8" Drag Bit (mud rotary) 4 1/4" ID; 8 1/4" Hole 24" OD Solid Auger		Sample Method 5' Continuous Sampler Grab from Auger	T.D. Borehole 93'	Well Installed? I-11
Remarks:				
Depth (ft)	Sample ID #	Gelger Reading (mV/hr)	Description	
5	WL-216 5'	0.12	0.0-26.0' <u>Landfill Debris</u> : trashy debris consisting of plastic, cloth, and glass; soil consisting of grayish brown to olive brown silty clay to gray, very fine-grained sand, and limestone rock; dry to moist.	
10	None Taken	Background (0.02-0.04)		
15	None Taken	Background (0.02-0.04)		
20	None Taken	Background (0.02-0.04)		
25	None Taken	None Taken		
30	None Taken	None Taken	26.0-60.0' <u>Native Alluvium</u> : gray, silty, very fine-grained sand grading to coarse-grained sand and gravel; moist to wet.  @ 48' wet	
35	None Taken	None Taken		
40	None Taken	None Taken		
45	None Taken	None Taken		
50	None Taken	None Taken		
55	None Taken	None Taken		
60	None Taken	None Taken		

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-216C		Project No./Name 07.0803035.003.002	Page: 2 of 2
Start/Finish Date 8/30/95 / 10/13/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling Drilling Service Company		Boring Location: Area 2 Ground Surface Elevation: 477.6 Northing: 1069819.16 Easting: 514925.06	
Driller Max Tinnin Bruce Murphy		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers LDH-80T Drill Rig, Large Diameter Auger			
Bit Size/Type 4 1/8" Drag Bit (mud rotary) 4 1/4" ID; 8 1/4" Hole 24" OD Solid Auger	Sample Method 5' Continuous Sampler Grab from Auger	T.D. Borehole 93'	Well Installed? I-11
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
65	None Taken	None Taken	65.0-93.0' <u>Native Alluvium</u> : gray, silty, very fine-grained sand grading to coarse-grained sand and gravel; moist to wet.
70	None Taken	None Taken	
75	None Taken	None Taken	
80	None Taken	None Taken	
85	None Taken	None Taken	
90	None Taken	None Taken	
95	None Taken	None Taken	Auger refusal @ 93.0'


Notes:

Radiological samples not collected during boring activities; downhole logging indicated elevated gamma readings from 1.0-6.5'.

Non-radiological samples not collected during boring activities.


Perched water not encountered during boring activities.

Groundwater encountered at 48 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-217		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/30/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 2	
Driller Bruce Murphy		Ground Surface Elevation: 474.7	
		Northing: 1069961.30	
		Easting: 515082.21	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 17'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-217 5'	Background (0.02-0.04)	0.0-17.0' <u>Landfill Debris</u> : trashy debris consisting of plastic, cloth, and paper; soil consisting of olive brown to dark gray silty clay, and crushed rock; dry to wet.  @ 12' wet  Abandoned boring @ 17.0'
10	WL-217 10'	Background (0.02-0.04)	
15	WL-217 15'	None Taken	
20	None Taken	None Taken	

Notes:

Radiological samples collected at 5 and 10 feet below ground surface.  
 Non-radiological samples not collected during boring activities.  
 Perched water encountered at 12 feet below ground surface.  
 Groundwater not encountered during boring activities.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-218		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/30/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor		Boring Location:	Area 2
Drilling Service Company		Ground Surface Elevation:	489.7
Driller		Northing:	1069462.69
Bruce Murphy		Easting:	514839.09
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 40'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mL/hr)	Description
5	WL-218 5'	Background (0.02-0.05)	0.0-37.0' <u>Landfill Debris</u> : trashy debris consisting of yard waste, wood, plastic, cloth, paper, wire, and metal; soil consisting of dark gray silty clay to fine-grained sand; dry to moist.
10	None Taken	Background (0.02-0.05)	
15	None Taken	Background (0.02-0.05)	
20	WL-218 20'	Background (0.02-0.05)	
25	WL-218 25'	Background (0.02-0.05)	
30	WL-218 30'	Background (0.02-0.05)	
35	WL-218 35'	Background (0.02-0.05)	37.0-40.0' <u>Native Alluvium</u> : Dark gray, fine-grained sand; moist. Boring terminated @ 40.0'
40	WL-218 40'	Background (0.02-0.05)	


Notes:

Radiological samples collected at 5 and 40 feet below ground surface.

Non-radiological samples collected at 25 feet below ground surface; priority pollutant sampling.

Perched water not encountered during boring activities.

Groundwater not encountered during boring activities.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-219		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 8/31/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 2 Ground Surface Elevation: 496.7	
Driller Bruce Murphy		Northing: 1069142.47 Easting: 514545.63	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Auger	T.D. Borehole 27'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mK/hr)	Description
5	WL-219 5'	Background (0.02-0.04)	0.0-27.0' <u>Landfill Debris</u> : trashy debris consisting of shingles, concrete, wood, plastic, cloth, paper, and metal; soil consisting of olive brown silt to dark gray silty clay; dry to wet.  @ 21' wet
10	WL-219 10'	Background (0.02-0.04)	
15	WL-219 15'	Background (0.02-0.04)	
20	WL-219 20'	Background (0.02-0.04)	
25	None Taken	None Taken	
30	None Taken	None Taken	Boring abandoned @ 27.0'


Notes:

Radiological samples collected at 5 and 10 feet below ground surface; grab perched water sample collected and analyzed.

Non-radiological samples collected at 25 feet below ground surface; grab perched water contingency sampling.

Perched water encountered at 21 feet below ground surface.

Groundwater not encountered during boring activities.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-220		Project No./Name 07.0803035.003.002	
Start/Finish Date 8/31/95		Page: 1 of 1	
Site Name and Location West Lake Landfill; Bridgeton, Missouri			
Drilling Contractor Drilling Service Company		Boring Location: Area 2	
Driller Bruce Murphy		Ground Surface Elevation: 503.9	
		Northing: 1069258.11	
		Easting: 514733.38	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 30'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geliger Reading (in R/hr)	Description
5	WL-220 5'	Background (0.02-0.04)	0.0-30.0' <u>Landfill Debris</u> : trashy debris consisting of yard waste, wood, plastic, cloth, paper, cardboard, insulation, concrete, and metal; soil consisting of dark gray silty clay, and crushed rock; dry to wet.
10	WL-220 10'	Background (0.02-0.04)	
15	WL-220 15'	Background (0.02-0.04)	
20	WL-220 20'	Background (0.02-0.04)	
25	WL-220 25'	Background (0.02-0.04)	
30	None Taken	None Taken	@ 23' wet Boring abandoned @ 30.0'

Notes:


Radiological samples collected at 5 and 25 feet below ground surface; grab perched water sample collected and analyzed.

Non-radiological samples not collected during boring activities.

Perched water encountered at 23 feet below ground surface.

Groundwater not encountered during boring activities.



Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-221		Project No./Name 07.0803035.003.002	
Start/Finish Date 9/1/95		Page: 1 of 1	
Site Name and Location West Lake Landfill; Bridgeton, Missouri			
Drilling Contractor Drilling Service Company		Boring Location: Area 2	
Driller Bruce Murphy		Ground Surface Elevation: 462.3	
		Northing: 1070567.35	
		Easting: 514459.37	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 35'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geiger Reading (mfR/hr)	Description
5	WL-221 5'	Background (0.02-0.04)	0.0-34.0' <u>Landfill Debris</u> : trashy debris consisting of glass, wood, wire, plastic, cloth, paper, and carpeting; soil consisting of dark gray and black silty clay to dark gray fine-grained sand; dry to moist.
10	WL-221 10'	Background (0.02-0.04)	
15	WL-221 15'	Background (0.02-0.04)	
20	WL-221 20'	Background (0.02-0.04)	
25	WL-221 25'	Background (0.02-0.04)	
30	WL-221 30'	Background (0.02-0.04)	
35	WL-221 35'	Background (0.02-0.04)	34.0-35.0' <u>Native Alluvium</u> : dark gray, silty, fine-grained sand; wet. @ 34' wet Boring terminated @ 35.0'


Notes:

Radiological samples collected at 5 and 35 feet below ground surface.

Non-radiological samples collected at 35 feet below ground surface; priority pollutant sampling.


Perched water not encountered during boring activities.

Groundwater encountered at 34 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-222		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/1/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor		Boring Location: Area 2	
Drilling Service Company		Ground Surface Elevation: 457.8	
Driller Bruce Murphy		Northing: 1070799.38	
		Easting: 514618.74	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 35'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geliger Reading (mils/hr)	Description
5	WL-222 5'	Background (0.02-0.04)	0.0-30.0' <u>Landfill Debris</u> : trashy debris consisting of plastic, cloth, paper, carpeting, wood, and metal; soil consisting of dark gray to black clay and silty clay to dark gray, silty, fine-grained sand; dry to moist.
10	WL-222 10'	Background (0.02-0.04)	
15	None Taken	Background (0.02-0.04)	
20	None Taken	Background (0.02-0.04)	
25	WL-222 25'	Background (0.02-0.04)	
30	None Taken	Background (0.02-0.04)	
35	WL-222 35'	Background (0.02-0.04)	30.0-35.0' <u>Native Alluvium</u> : dark gray, silty, fine-grained sand: wet. Boring terminated @ 35.0'

Notes:

Radiological samples collected at 5 and 30 feet below ground surface.  
 Non-radiological samples collected at 30 feet below ground surface; priority pollutant and priority pollutant duplicate sampling.  
 Perched water not encountered during boring activities.  
 Groundwater encountered at 30 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-223		Project No./Name 07.0803035.003.002	
Start/Finish Date 9/5/95		Page: 1 of 1	
Site Name and Location West Lake Landfill; Bridgeton, Missouri			
Drilling Contractor Drilling Service Company		Boring Location: Area 2	
Driller Bruce Murphy		Ground Surface Elevation: 462.2	
		Northing: 1070745.71	
		Easting: 514734.14	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 23'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Caliper Reading (in R/hr)	Description
5	WL-223 5'	Background (0.01-0.03)	0.0-22.0' <u>Landfill Debris</u> : trashy debris consisting of wire, wood, plastic, cloth, rubber, and paper; soil consisting of brownish yellow silt to dark gray silty clay and silty fine-grained sand; dry to moist.
10	WL-223 10'	Background (0.01-0.03)	
15	WL-223 15'	Background (0.01-0.03)	
20	WL-223 20'	Background (0.01-0.03)	
25	WL-223 23'	Background (0.01-0.03)	22.0-23.0' <u>Native Alluvium</u> : dark gray, fine-grained sand; moist. Boring terminated @ 23.0'

Notes:

Radiological samples collected at 5 and 22 feet below ground surface; downhole logging indicated elevated gamma readings from 4.0-5.5'.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater not encountered during boring activities.

# Soil Boring Log



**McLaren  
Hart**

Boring No. WL-224		Project No./Name 07.0803035.003.002	Page: 1 of 3
Start/Finish Date 9/14/95 / 10/19/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 2	
Drilling Service Company		Ground Surface Elevation: 468.4	
Driller Max Timmin		Northing: 1070485.74	
Bruce Murphy		Easting: 515601.73	
McLaren/Hart Geologist/Office Tim Biggs / St. Louis			

**Drilling Equipment**  
CME-55 Drill Rig, Hollow Stem Augers  
LDH-80T Drill Rig, Large Diameter Auger

Bit Size/Type 4 1/8" Drag Bit (mud rotary) 4 1/4" ID; 8 1/4" Hole 24" OD Solid Auger	Sample Method 5' Continuous Sampler Grab from Auger	T.D. Borehole 135.5	Well Installed? D-13
---	---	------------------------	-------------------------

**Remarks:**

Depth (ft)	Sample ID #	Geiger Reading (uR/hr)	Description
5	WL-224 5'	Background (0.02-0.04)	0.0-33.0' <u>Landfill Debris</u> : trashy debris consisting of rubber, wood, plastic, cloth, paper, glass, and metal; soil consisting of brownish yellow silt and dark gray clayey silt to silty fine-grained sand; dry to moist.
10	WL-224 10'	Background (0.02-0.04)	
15	WL-224 15'	Background (0.02-0.04)	
20	WL-224 20'	Background (0.02-0.04)	
25	WL-224 25'	Background (0.02-0.04)	
30	WL-224 30'	Background (0.02-0.04)	
35	WL-224 35'	Background (0.02-0.04)	@ 33' wet
40	None Taken	Background (0.02-0.04)	33.0-65.0' <u>Native Alluvium</u> : dark gray clayey silt grading to fine to coarse grained sand, and coal; wet.
45	None Taken	Background (0.02-0.04)	
50	None Taken	Background (0.02-0.04)	
55	None Taken	None Taken	
60	None Taken	None Taken	

# Soil Boring Log



**McLaren  
Hart**

Boring No.  
WL-224

Project No./Name  
07.0803035.003.002

Page:  
2 of 3

Start/Finish Date  
9/14/95 / 10/19/95

Site Name and Location  
West Lake Landfill; Bridgeton, Missouri

Drilling Contractor  
Hart Environmental Drilling  
Drilling Service Company

Boring Location: Area 2  
Ground Surface Elevation: 468.4  
Northing: 1070485.74  
Easting: 515601.73

Driller  
Max Tinnin  
Bruce Murphy

McLaren/Hart Geologist/Office  
Tim Biggs / St. Louis

## Drilling Equipment

CME-55 Drill Rig, Hollow Stem Augers  
LDH-80T Drill Rig, Large Diameter Auger

Bit Size/Type  
4 1/8" Drag Bit (mud rotary)  
4 1/4" ID; 8 1/4" Hole  
24" OD Solid Auger


Sample Method  
5' Continuous Sampler  
Grab from Auger

T.D. Borehole  
135.5

Well Installed?  
D-13


## Remarks:

Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description
65	None Taken	None Taken	65.0-125.0' <u>Native alluvium</u> : dark gray clayey silt grading to fine to coarse grained sand, and coal; wet.
70	None Taken	None Taken	
75	None Taken	None Taken	
80	None Taken	None Taken	
85	None Taken	None Taken	
90	None Taken	None Taken	
95	None Taken	None Taken	
100	None Taken	None Taken	
105	None Taken	None Taken	
110	None Taken	None Taken	
115	None Taken	None Taken	

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-224		Project No./Name 07.0803035.003.002	Page: 3 of 3
Start/Finish Date 9/14/95 / 10/19/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling Drilling Service Company		Boring Location: Area 2 Ground Surface Elevation: 468.4 Northing: 1070485.74 Easting: 515601.73	
Driller Max Timmin Bruce Murphy		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers LDH-80T Drill Rig, Large Diameter Auger			
Bit Size/Type 4 1/8" Drag Bit (mud rotary) 4 1/4" ID; 8 1/4" Hole 24" OD Solid Auger	Sample Method 5' Continuous Sampler Grab from Auger	T.D. Borehole 135.5	Well Installed? D-13
Remarks:			
Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description
120	None Taken	None Taken	125.0-135.5' Native Alluvium: dark gray clayey silt grading to fine to coarse grained sand, and coal; wet.  Auger refusal @ 135.5' (bedrock)
125	None Taken	None Taken	
130	None Taken	None Taken	
135	None Taken	None Taken	
140	None Taken	None Taken	


Notes:

Radiological samples collected at 5 and 35 feet below ground surface.  
 Non-radiological samples not collected during boring activities.  
 Perched water not encountered during boring activities.  
 Groundwater encountered at 33 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-225		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/14/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor		Boring Location: Area 2	
Drilling Service Company		Ground Surface Elevation: 468.2	
Driller Bruce Murphy		Northing: 1070576.93	
		Easting: 515632.66	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 37'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description
5	WL-225 5'	Background (0.02-0.04)	0.0-37.0' <u>Landfill Debris</u> : trashy debris consisting of rubber, shingles, wood, plastic, cloth, paper, glass, concrete, and metal; soil consisting of dark gray, slightly sandy, clayey silt; dry to wet.  @ 31.5' wet
10	WL-225 10'	Background (0.02-0.04)	
15	WL-225 15'	Background (0.02-0.04)	
20	WL-225 20'	Background (0.02-0.04)	
25	WL-225 25'	Background (0.02-0.04)	
30	WL-225 30'	Background (0.02-0.04)	
35	WL-225 35'	Background (0.02-0.04)	
40	None Taken	None Taken	Boring terminated @ 37.0'

Notes:

Radiological samples collected at 5 and 35 feet below ground surface.  
 Non-radiological samples not collected during boring activities.  
 Perched water not encountered during boring activities.  
 Groundwater encountered at 31.5 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-226		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/15/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 2 Ground Surface Elevation: 467.5	
Driller Bruce Murphy		Northing: 1070536.03 Easting: 514992.10	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 43'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mL/hr)	Description
5	WL-226 5'	Background (0.02-0.04)	0.0-42.0' <u>Landfill Debris</u> : trashy debris consisting of wood, rubber, wire, plastic, cloth, and paper; soil consisting of dark gray, slightly sandy, clayey silt to fine-grained sand; dry to moist.
10	WL-226 10'	Background (0.02-0.04)	
15	WL-226 15'	0.11	
20	WL-226 20'	Background (0.02-0.04)	
25	WL-226 25'	Background (0.02-0.04)	
30	WL-226 30'	Background (0.02-0.04)	
35	WL-226 35'	Background (0.02-0.04)	
40	WL-226 40'	Background (0.02-0.04)	
45	WL-226 43'	None Taken	@ 42' wet 42.0-43.0' <u>Native Alluvium</u> : dark gray fine-grained sand; wet. Boring terminated @ 43.0'

Notes:


Radiological samples collected at 10 and 20 feet below ground surface; downhole logging indicated elevated gamma readings from 2.0-3.5' and 6.0-16.0'.

Non-radiological samples collected at 43 feet below ground surface; priority pollutant sampling.

Perched water not encountered during boring activities.

Groundwater encountered at 42 feet below ground surface.



Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-227		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/15/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 2 Ground Surface Elevation: 462	
Driller Bruce Murphy		Northing: 1070685.99 Easting: 515258.39	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 40'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-227 5'	Background (0.02-0.04)	0.0-40.0' <u>Landfill Debris</u> : trashy debris consisting of wood, rubber, plastic, cloth, glass, carpeting, metal, and paper; soil consisting of brown and dark gray silty clay to dark gray fine-grained sand; dry to wet.
10	WL-227 10'	Background (0.02-0.04)	
15	WL-227 15'	Background (0.02-0.04)	
20	WL-227 20'	Background (0.02-0.04)	
25	WL-227 25'	Background (0.02-0.04)	
30	WL-227 30'	Background (0.02-0.04)	
35	WL-227 35'	Background (0.02-0.04)	@ 28' wet
40	WL-227 40'	Background (0.02-0.04)	40.0' <u>Native Alluvium</u> : dark gray fine-grained sand; wet. Boring terminated @ 40.0'


Notes:

Radiological samples collected at 5 and 40 feet below ground surface.

Non-radiological samples collected at 40 feet below ground surface; priority pollutant sampling.

Perched water not encountered during boring activities.

Groundwater encountered at 28 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-228		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/15/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 2 Ground Surface Elevation: 441.6	
Driller Max Tinnin		Northing: 1071044.35 Easting: 514724.16	
Drilling Equipment CME-55 Drill Rig; Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5' Continuous Sampler	T.D. Borehole 29.3'	Well Installed? S-8
Remarks:			
Depth (ft)	Sample ID #	Geliger Reading (mR/hr)	Description
5	WL-228 5'	Background (0.01-0.04)	0.0-29.3' <u>Native Alluvium</u> : olive brown sandy silt and silty clay grading to dark gray medium to coarse-grained sand; dry to wet.  @ 10' wet    Boring terminated @ 29.3'
10	WL-228 10'	Background (0.01-0.04)	
15	WL-228 15'	Background (0.01-0.04)	
20	WL-228 20'	Background (0.01-0.04)	
25	WL-228 25'	Background (0.01-0.04)	
30	None Taken	Background (0.01-0.04)	

Notes:

Radiological samples collected at 5 and 15 feet below ground surface.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.


Groundwater encountered at 10 feet below ground surface.

# Soil Boring Log




**McLaren  
Hart**

Boring No. WL-229		Project No./Name 07.0803035.003.002		Page: 1 of 2
Start/Finish Date 9/18/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri		
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 2		
Driller Max Tinnin		Ground Surface Elevation: 448.5		
		Northing: 1069329.26		
		Easting: 514268.59		
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis		
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5' Continuous Sampler	T.D. Borehole 55.6'	Well Installed? 1-9	
Remarks:				
Depth (ft)	Sample ID #	Gelger Reading (nK/hr)	Description	
5	WL-229 5	Background (0.01-0.04)	0.0-5.0' <u>Landfill Debris</u> : soil consisting of brown silt, and asphalt; no trashy debris encountered; dry.	
10	None Taken	Background (0.01-0.04)	5.0-56.0' <u>Native Alluvium</u> : dark gray, silty, fine-grained sand grading to coarse-grained sand with gravel; moist to wet.  @ 16' wet	
15	None Taken	Background (0.01-0.04)		
20	WL-229 20'	Background (0.01-0.04)		
25	WL-229 25'	Background (0.01-0.04)		
30	WL-229 30'	Background (0.01-0.04)		
35	None Taken	None Taken		
40	None Taken	None Taken		
45	None Taken	None Taken		
50	None Taken	None Taken		

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-229		Project No./Name 07.0803035.003.002	Page: 2 of 2
Start/Finish Date 9/18/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Hart Environmental Drilling		Boring Location: Area 2	
		Ground Surface Elevation: 448.5	
Driller Max Tinnin		Northing: 1069329.26	
		Easting: 514268.59	
Drilling Equipment CME-55 Drill Rig, Hollow Stem Augers		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 4 1/4" ID; 8 1/4" Hole	Sample Method 5' Continuous Sampler	T.D. Borehole 55.6'	Well Installed? I-9
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (nR/hr)	Description
55	None Taken	None Taken	50.0-55.6' <u>Native Alluvium</u> : dark gray, silty, fine-grained sand grading to coarse-grained sand with gravel; moist to wet.
60	None Taken	None Taken	Boring terminated @ 55.6'

Notes:

Radiological samples collected at 5 and 20 feet below ground surface.  
 Non-radiological samples not collected during boring activities.  
 Perched water not encountered during boring activities.  
 Groundwater encountered at 16 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-230		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/18/95		Site Name and Location West Lake Landfill, Bridgeton, Missouri	
Drilling Contractor		Boring Location: Area 2	
Drilling Service Company		Ground Surface Elevation: 463.3	
Driller Bruce Murphy		Northing: 1070716.09	
		Easting: 515139.66	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 35'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mL/hr)	Description
5	WL-230 5'	Background (0.02-0.04)	0.0-32.0' <u>Landfill Debris</u> : trashy debris consisting of plastic, cloth, wire, glass, carpeting, metal, and paper; soil consisting of olive brown silt, dark gray clayey silt, and dark gray, silty, fine-grained sand; dry to wet.  @ 16' soil discolored; petroleum odor; OVM reading greater than 10 X background.  @ 29' wet
10	WL-230 10'	Background (0.02-0.04)	
15	WL-230 15'	Background (0.02-0.04)	
20	WL-230 20'	Background (0.02-0.04)	
25	WL-230 25'	Background (0.02-0.04)	
30	WL-230 30'	Background (0.02-0.04)	
35	WL-230 35'	Background (0.02-0.04)	32.0-35.0' <u>Native Alluvium</u> : dark gray, silty, fine-grained sand; wet. Boring terminated @ 35.0'


Notes:

Radiological samples collected at 5 and 35 feet below ground surface.

Non-radiological samples collected at 16 and 35 feet below ground surface; contingency sampling.

Perched water not encountered during boring activities.

Groundwater encountered at 29 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-231		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/18/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Ground Surface Elevation:	Area 2 464.8
Driller Bruce Murphy		Northing: Easting:	1070850.73 515007.27
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 40'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description
5	WL-231 5'	Background (0.02-0.04)	0.0-40.0' <u>Landfill Debris</u> : trashy debris consisting of plastic, cloth, glass, and paper; soil consisting of brownish gray silt, dark gray and black clayey silt to dark gray, silty, fine-grained sand, and crushed rock; dry to wet.
10	WL-231 10'	Background (0.02-0.04)	
15	WL-231 15'	Background (0.02-0.04)	
20	WL-231 20'	Background (0.02-0.04)	
25	WL-231 25'	Background (0.02-0.04)	
30	WL-231 30'	Background (0.02-0.04)	
35	WL-231 35'	Background (0.02-0.04)	@ 31.5' wet
40	None Taken	None Taken	Boring abandoned @ 40.0'


Notes:

Radiological samples collected at 5 and 10 feet below ground surface; downhole logging indicated elevated gamma readings from 4.5-7.5.

Non-radiological samples collected at 31 feet below ground surface; contingency grab perched water sampling.

Perched water not encountered during boring activities.

Groundwater encountered at 31.5 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-233		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/19/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 2	
Driller Bruce Murphy		Ground Surface Elevation: 489.2	
		Northing: 1069542.40	
		Easting: 514609.19	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 42.5'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-233 5'	Background (0.02-0.04)	0.0-42.5' Landfill Debris: trashy debris consisting of wood, plastic, cloth, wire, limestone, rubber, metal, and paper; soil consisting of gray clay, dark gray to black silt, and dark gray, silty, fine-grained sand; dry to wet.
10	WL-233 10'	Background (0.02-0.04)	
15	WL-233 15'	Background (0.02-0.04)	
20	WL-233 20'	Background (0.02-0.04)	
25	WL-233 25'	Background (0.02-0.04)	
30	WL-233 30'	Background (0.02-0.04)	
35	WL-233 35'	Background (0.02-0.04)	
40	WL-233 40'	Background (0.02-0.04)	@ 20' OVM readings greater than 10 X background
45	WL-233 45'	Background (0.02-0.04)	@ 37' wet
Boring terminated @ 42.5'			


Notes:

Radiological samples collected at 27 and 30 feet below ground surface; downhole logging indicated elevated gamma readings from 18.0-24.5'.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater encountered at 37 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-234		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/19/95 / 9/20/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor		Boring Location: Area 2	
Drilling Service Company		Ground Surface Elevation: 480	
Driller Bruce Murphy		Northing: 1069757.62 Easting: 514428.12	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 42'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-234 5'	0.08	0.0-39.0' <u>Landfill Debris</u> : trashy debris consisting of wood, plastic, and glass; soil consisting of brown silt, dark gray clayey silt and silty clay to dark gray, silty, fine-grained sand and crushed rock; dry to moist.
10	WL-234 10'	3.0	
15	WL-234 15'	0.15	
20	WL-234 20'	Background (0.02-0.04)	
25	WL-234 25'	Background (0.02-0.04)	
30	WL-234 30'	Background (0.02-0.04)	
35	WL-234 35'	Background (0.02-0.04)	39.0-42.0' <u>Native Alluvium</u> : dark gray plastic clay grading to clayey silt; moist.
40	WL-234 40'	Background (0.02-0.04)	
45	WL-234 42'	Background (0.02-0.04)	
Boring terminated @ 42.0'			

Notes:


Radiological samples collected at 10 and 20 feet below ground surface; duplicate samples collected and analyzed; downhole logging indicated elevated gamma readings from 0.0-15.0'.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater not encountered during boring activities.



Soil Boring Log		 <b>McLaren/Hart</b>	
Boring No. WL-235		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/20/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 2 Ground Surface Elevation: 481.1	
Driller Bruce Murphy		Northing: 1069615.23 Easting: 514418.87	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 30'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-235 5'	Background (0.02-0.04)	0.0-30.0' <u>Landfill Debris</u> : trashy debris consisting of wood, metal, paper, wire, cloth, insulation, plastic, and glass; soil consisting of dark gray silty clay to clayey and silty, fine-grained sand; dry to wet.  @ 25' wet
10	WL-235 10'	Background (0.02-0.04)	
15	WL-235 15'	Background (0.02-0.04)	
20	None Taken	Background (0.02-0.04)	
25	None Taken	Background (0.02-0.04)	
30	WL-235 30'	Background (0.02-0.04)	Boring abandoned @ 30.0'


Notes:

Radiological samples collected at 5 and 30 feet below ground surface; downhole logging indicated elevated gamma readings from 21.0-24.0'.

Non-radiological samples not collected during boring activities.

Perched water encountered at 25 feet below ground surface.

Groundwater not encountered during boring activities.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-236		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/21/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 2 Ground Surface Elevation: 484.3	
Driller Bruce Murphy		Northing: 1069399.29 Easting: 514384.13	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 37'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description
5	WL-236 5'	Background (0.01-0.04)	0.0-37.0' Landfill Debris: trashy debris consisting of wood, metal, paper, wire, carpeting, rubber, cloth, insulation, and plastic; soil consisting of dark gray clay to silty clay; dry to moist.
10	None Taken	Background (0.01-0.04)	
15	None Taken	Background (0.01-0.04)	
20	None Taken	Background (0.01-0.04)	
25	None Taken	Background (0.01-0.04)	
30	WL-236 30'	Background (0.01-0.04)	
35	WL-236 35'	Background (0.01-0.04)	@ 35' wet
40	None Taken	Background (0.01-0.04)	Auger refusal @ 37.0'


Notes:

Radiological samples collected at 5 and 35 feet below ground surface.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater encountered at 35 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-237		Project No./Name 07.0803035.003.002	
Start/Finish Date 9/22/95		Page: 1 of 1	
Site Name and Location West Lake Landfill: Bridgeton, Missouri			
Boring Location: Area 2			
Ground Surface Elevation: 473.9			
Northing: 1070069.42			
Easting: 515161.88			
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 40'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Celiger Reading (mR/hr)	Description
5	None Taken	Background (0.02)	0.0-34.0' <u>Landfill Debris</u> : trashy debris consisting of wood, medical waste, plastic, concrete, brick, metal, and paper; soil consisting of brown silt, dark gray fine-grained sand, and crushed rock; dry to moist. @ 10' OVM readings greater than 10 X background.
10	None Taken	Background (0.02)	
15	None Taken	Background (0.02)	
20	None Taken	Background (0.02)	
25	None Taken	Background (0.02)	
30	None Taken	Background (0.02)	
35	None Taken	Background (0.02)	34.0-40.0' <u>Native Alluvium</u> : dark gray plastic clay grading to clayey silt; moist.
40	None Taken	Background (0.02)	Boring terminated @ 40.0'

Notes:

- Radiological samples not collected during boring activities.
- Non-radiological samples not collected during boring activities.
- Perched water not encountered during boring activities.
- Groundwater not encountered during boring activities.

# Soil Boring Log



**McLaren/Hart**

Boring No. <b>WL-238</b>		Project No./Name <b>07.0803035.003.002</b>		Page: <b>1 of 1</b>
Start/Finish Date <b>9/22/95</b>		Site Name and Location <b>West Lake Landfill, Bridgeton, Missouri</b>		
Drilling Contractor <b>Drilling Service Company</b>		Boring Location: <b>Area 2</b>		
Driller <b>Bruce Murphy</b>		Ground Surface Elevation: <b>466.2</b>		
		Northing: <b>1070705.96</b>		
		Easting: <b>514916.28</b>		
Drilling Equipment <b>LDH-80T Drill Rig, Large Diameter Auger</b>		McLaren/Hart Geologist/Office <b>Tim Biggs / St. Louis</b>		
Bit Size/Type <b>24" OD Solid Auger</b>	Sample Method <b>Grab from Augers</b>	T.D. Borehole <b>34'</b>	Well Installed? <b>None Installed</b>	
Remarks:				
Depth (ft)	Sample ID #	Gelger Reading (min/hr)	Description	
5	None Taken	Background (0.04)	<b>0.0-27.0' Landfill Debris:</b> trashy debris consisting of wood, shredded tires, and wire; soil consisting of brown silt and dark gray fine-grained sand; dry to moist.  <b>@ 10.0-25.0'</b> soil discolored; petroleum odor; OVM reading greater than 10 X background.	
10	None Taken	Background (0.04)		
15	None Taken	Background (0.04)		
20	None Taken	Background (0.04)		
25	None Taken	Background (0.04)		
30	None Taken	None Taken	<b>27.0-34.0' Native Alluvium:</b> dark gray fine-grained sand; moist to wet.	
35	None Taken	Background (0.04)	<b>@ 34' wet</b> <b>Boring terminated @ 34.0'</b>	


## Notes:

Radiological samples not collected during boring activities; downhole logging indicated elevated gamma readings from 3.5-9.0'.

Non-radiological samples not collected during boring activities.


Perched water not encountered during boring activities.

Groundwater encountered at 34 feet below ground surface.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-240		Project No./Name 07.0803035.003.002	
Start/Finish Date 9/28/95		Page: 1 of 1	
Site Name and Location West Lake Landfill; Bridgeton, Missouri			
Drilling Contractor Drilling Service Company		Boring Location: Area 2	
Driller Bruce Murphy		Ground Surface Elevation: 468.5	
		Northing: 1070320.97	
		Easting: 515315.69	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 11'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Gelger Reading (mR/hr)	Description
5	WL-240 5'	Background (0.01-0.04)	0.0-11.0' <u>Landfill Debris</u> : trashy debris consisting of plastic and wood; soil consisting of dark gray silty clay and crushed rock; dry to wet @ 4.5' wet
10	None Taken	Background (0.01-0.04)	
15	None Taken	Background (0.01-0.04)	
Boring abandoned @ 11.0'			

Notes:

Radiological samples not collected during boring activities.  
 Non-radiological samples not collected during boring activities.  
 Perched water encountered at 4.5 feet below ground surface.  
 Groundwater not encountered during boring activities.

Soil Boring Log		 <b>McLaren Hart</b>	
Boring No. WL-241		Project No./Name 07.0803035.003.002	Page: 1 of 1
Start/Finish Date 9/28/95		Site Name and Location West Lake Landfill; Bridgeton, Missouri	
Drilling Contractor Drilling Service Company		Boring Location: Area 2 Ground Surface Elevation: 469.6	
Driller Bruce Murphy		Northing: 1070319.84 Easting: 515100.73	
Drilling Equipment LDH-80T Drill Rig, Large Diameter Auger		McLaren/Hart Geologist/Office Tim Biggs / St. Louis	
Bit Size/Type 24" OD Solid Auger	Sample Method Grab from Augers	T.D. Borehole 40'	Well Installed? None Installed
Remarks:			
Depth (ft)	Sample ID #	Geiger Reading (mR/hr)	Description
5	WL-241 5'	Background (0.01-0.04)	0.0-40.0' Landfill Debris: trashy debris consisting of glass, insulation, wood, cardboard, paper, wire, rubber, plastic, and wood; soil consisting of dark gray clay and silty clay to silty fine-grained sand, and crushed rock; dry to wet.
10	WL-241 10'	Background (0.01-0.04)	
15	WL-241 15'	Background (0.01-0.04)	
20	WL-241 20'	Background (0.01-0.04)	
25	WL-241 25'	Background (0.01-0.04)	
30	WL-241 30'	Background (0.01-0.04)	
35	WL-241 35'	Background (0.01-0.04)	
40	WL-241 40'	Background (0.01-0.04)	@ 40' wet Boring abandoned @ 40.0'

Notes:

Radiological samples collected at 5 and 15 feet below ground surface; downhole logging indicated elevated gamma readings from 4.0-8.5'.

Non-radiological samples not collected during boring activities.

Perched water not encountered during boring activities.

Groundwater encountered at 40 feet below ground surface.



---

**Area 1 Soil Boring  
Downhole Gamma Logs**

---

(C:\WESTLAKE\WL1 01.GB0)

COLOG



(C:\WESTLAKE\WL1 01.GB0)


COLOG



(C:\WESTLAKE\WL102.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →


(C:\WESTLAKE\WL102.GB0)

COLOG

(C:\WESTLAKE\WL103.GB0)

COLOG

NGamma  
CPM 0 600000



NGamma  
CPM 0 600000


(C:\WESTLAKE\WL103.GB0)

COLOG

(C:\WESTLAKE\WL104.GB0)

COLOG

← 0 NGamma CPM 600000 →




← 0 NGamma CPM 600000 →

(C:\WESTLAKE\WL104.GB0)

COLOG

(C:\WESTLAKE\WL105.GB4)

COLOG



NGamma  
CPM


0 600000

(C:\WESTLAKE\WL105.GB4)

COLOG

(C:\WESTLAKE\WLI4.GB0)

COLOG



NGamma  
CPM



600000

(C:\WESTLAKE\WLI4.GB0)

COLOG

(C:\WESTLAKE\WLI4D.GB0)

COLOG



(C:\WESTLAKE\WL105D.GB0)

COLOG

NGamma  
CPM

600000

0

10

20

30

40

50

60

70

80

90

100

NGamma  
CPM

600000


0

(C:\WESTLAKE\WL105D.GB0)

COLOG

(C:\WESTLAKE\WLS5.GB0)

COLOG





(C:\WESTLAKE\WLS5.GB0)

COLOG





(C:\WESTLAKE\WLS5D.GB0)

COLOG



(C:\WESTLAKE\WL106.GB0)

COLOG





(C:\WESTLAKE\WL106.GB0)

COLOG

(C:\WESTLAKE\WL106A.GB0)

COLOG



(C:\WESTLAKE\WL106A.GB0)

COLOG

(C:\WESTLAKE\WL107.GB0)

COLOG

NGamma  
CPM

600000

0

5

10

15

20

25

30

35

40

45

50

NGamma  
CPM

600000



0

(C:\WESTLAKE\WL107.GB0)

COLOG

(C:\WESTLAKE\WL108.GB0)

COLOG





(C:\WESTLAKE\WL108.GB0)

COLOG

(C:\WESTLAKE\WL109.GB0)

COLOG



(C:\WESTLAKE\WL109.GB0)

COLOG

(C:\WESTLAKE\WL109B.GB0)

COLOG

NGamma  
CPM

600000

0

0

5

10

15

20

25

30

35

40

45

NGamma  
CPM

600000

0

(C:\WESTLAKE\WL109B.GB0)

COLOG

(C:\WESTLAKE\WL109C.GB0)

COLOG

NGamma  
CPM

600000

0

0  
5  
10  
15  
20  
25  
30  
35  
40  
45  
50  
55

NGamma  
CPM

600000

0

(C:\WESTLAKE\WL109C.GB0)

COLOG



(C:\WESTLAKE\WL109D.GB0)

COLOG

NGamma  
CPM

600000

0

0

5

10

15

20

25

30

35

40

45

50

55

NGamma  
CPM

600000

0

(C:\WESTLAKE\WL109D.GB0)

COLOG

(C:\WESTLAKE\WL110.GB0)

COLOG

NGamma  
CPM

600000

0

5

10

15

20

25

30

35

40

45

50

NGamma  
CPM

600000



0

(C:\WESTLAKE\WL110.GB0)

COLOG

(C:\WESTLAKE\WL111.GB0)


COLOG



(C:\WESTLAKE\WL112.GBI)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →


(C:\WESTLAKE\WL112.GBI)

COLOG

(C:\WESTLAKE\WL113.GB0)

COLOG

0 NGamma CPM 600000



0 NGamma CPM 600000


(C:\WESTLAKE\WL113.GB0)

COLOG

(C:\WESTLAKE\WL114.GB0)

COLOG

← 0 NGamma CPM 600000 →




← 0 NGamma CPM 600000 →

(C:\WESTLAKE\WL114.GB0)

COLOG

(C:\WESTLAKE\WL115.GB0)

COLOG



NGamma CPM 600000


(C:\WESTLAKE\WL115.GB0)

COLOG

(C:\WESTLAKE\WL116.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →



(C:\WESTLAKE\WL116.GB0)

COLOG





(C:\WESTLAKE\WL117.GB0)

COLOG





(C:\WESTLAKE\WL118.GB0)

COLOG



(C:\WESTLAKE\WL119.GB0)

COLOG




(C:\WESTLAKE\WL119.GB0)

COLOG

(C:\WESTLAKE\WL1 20.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →

(C:\WESTLAKE\WL1 20.GB0)

COLOG

---


**Area 2 Soil Boring  
Downhole Gamma Logs**

---

(C:\WESTLAKE\WL201.GB0)

COLOG

← 0 NGamma CPM 600000 →





← 0 NGamma CPM 600000 →

(C:\WESTLAKE\WL201.GB0)

COLOG

(C:\WESTLAKE\WL202.GB0)

COLOG




(C:\WESTLAKE\WL202.GB0)

COLOG

(C:\WESTLAKE\WL203.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →

(C:\WESTLAKE\WL203.GB0)


COLOG



(C:\WESTLAKE\WL204.GB1)

COLOG

NGamma  
0 CPM 600000





NGamma  
0 CPM 600000

(C:\WESTLAKE\WL204.GB1)

COLOG

(C:\WESTLAKE\WL204T.GB0)


COLOG



(C:\WESTLAKE\WL205.GB0)

COLOG

← 0 NGamma CPM 600000 →





← 0 NGamma CPM 600000 →

(C:\WESTLAKE\WL205.GB0)

COLOG

(C:\WESTLAKE\WLD6.GB0)

COLOG



(C:\WESTLAKE\WLD6.GB0)

COLOG

W L D60

NGamma  
CPM

600000

0  
10  
20  
30  
40  
50  
60  
70  
80  
90  
100

0  
NGamma  
CPM



600000

(C:\WESTLAKE\WLD60.GB0)

COLOG

(C:\WESTLAKE\WL207.GB0)

COLOG




(C:\WESTLAKE\WL207.GB0)

COLOG

(C:\WESTLAKE\WL207D.GB0)


COLOG



(C:\WESTLAKE\WL208.GB2)

COLOG

NGamma  
CPM 0 600000



NGamma  
CPM 0 600000



(C:\WESTLAKE\WL208.GB2)

COLOG




(C:\WESTLAKE\WL209.GB0)

COLOG



(C:\WESTLAKE\WL210.GB0)

COLOG



NGamma  
CPM

0 600000


(C:\WESTLAKE\WL210.GB0)

COLOG

(C:\WESTLAKE\WL210T.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →

(C:\WESTLAKE\WL210T.GB0)

COLOG



**COLOG**



(C:\WESTLAKE\WL211.GBO)

(C:\WESTLAKE\WL21 2.GB0)

COLOG




(C:\WESTLAKE\WL21 2.GB0)

COLOG

(C:\WESTLAKE\WL21 3.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →


(C:\WESTLAKE\WL21 3.GB0)

COLOG

(C:\WESTLAKE\WL21 4.GB0)

COLOG

← 0 NGamma CPM 600000 →





← 0 NGamma CPM 600000 →

(C:\WESTLAKE\WL21 4.GB0)

COLOG

(C:\WESTLAKE\WL216.GB0)

COLOG



(C:\WESTLAKE\WL216.GB0)


COLOG



(C:\WESTLAKE\WL21 6C.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →


(C:\WESTLAKE\WL21 6C.GB0)

COLOG

(C:\WESTLAKE\WL217.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →


(C:\WESTLAKE\WL217.GB0)

COLOG

(C:\WESTLAKE\WL218.GB0)

COLOG

NGamma  
CPM 0 600000





NGamma  
CPM 0 600000

(C:\WESTLAKE\WL218.GB0)

COLOG

(C:\WESTLAKE\WL219A.GB0)

COLOG




(C:\WESTLAKE\WL219A.GB0)

COLOG

(C:\WESTLAKE\WL220.GB2)

COLOG

← 0 NGamma CPM 600000 →




← 0 NGamma CPM 600000 →

(C:\WESTLAKE\WL220.GB2)

COLOG

(C:\WESTLAKE\WL221.GB0)

COLOG




(C:\WESTLAKE\WL221.GB0)

COLOG

(C:\WESTLAKE\WL222.GB0)

COLOG

← 0 NGamma CPM 600000 →





← 0 NGamma CPM 600000 →

(C:\WESTLAKE\WL222.GB0)

COLOG

(C:\WESTLAKE\WL223.GB0)


COLOG





(C:\WESTLAKE\WL224.GB1)

COLOG



NGamma CPM



0 600000

(C:\WESTLAKE\WL224.GB1)

COLOG

(C:\WESTLAKE\WL225.GB1)

COLOG




(C:\WESTLAKE\WL225.GB1)

COLOG

(C:\WESTLAKE\WL226.GB5)

COLOG



NGamma  
CPM


0 600000

(C:\WESTLAKE\WL226.GB5)

COLOG

(C:\WESTLAKE\WL227.GB0)

COLOG




(C:\WESTLAKE\WL227.GB0)

COLOG

(C:\WESTLAKE\WL228.GB0)

COLOG

← 0 NGamma CPM 600000 →





← 0 NGamma CPM 600000 →

(C:\WESTLAKE\WL228.GB0)

COLOG

(C:\WESTLAKE\WL229.GB0)

COLOG



(C:\WESTLAKE\WL229D.GB0)

COLOG

NGamma  
CPM

600000

0  
5  
10  
15  
20  
25  
30  
35  
40  
45  
50

NGamma  
CPM


600000

(C:\WESTLAKE\WL229D.GB0)

COLOG

(C:\WESTLAKE\WL230.GB0)

COLOG



NGamma  
CPM

0 600000



(C:\WESTLAKE\WL230.GB0)

COLOG



(C:\WESTLAKE\WL231.GB0)

COLOG




(C:\WESTLAKE\WL231.GB0)

COLOG

(C:\WESTLAKE\WL232.GB0)

COLOG




0 NGamma CPM 600000

(C:\WESTLAKE\WL232.GB0)

COLOG

(C:\WESTLAKE\WL233.GB0)

COLOG



NGamma CPM


0 600000

(C:\WESTLAKE\WL233.GB0)

COLOG

(C:\WESTLAKE\WL234.GB0)

COLOG



NGamma  
CPM

0 600000


(C:\WESTLAKE\WL234.GB0)

COLOG

(C:\WESTLAKE\WL235.GB0)

COLOG

← 0 NGamma CPM 600000 →




← 0 NGamma CPM 600000 →

(C:\WESTLAKE\WL235.GB0)

COLOG



(C:\WESTLAKE\WL236.GB0)

COLOG



(C:\WESTLAKE\WL237.GB0)


COLOG



COLOG

(C:\WESTLAKE\WL238.GB0)

COLOG



(C:\WESTLAKE\WL238.GB0)


COLOG



(C:\WESTLAKE\WL239.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →


(C:\WESTLAKE\WL239.GB0)

COLOG

(C:\WESTLAKE\WL240.GB0)

COLOG

← 0 NGamma CPM 600000 →





← 0 NGamma CPM 600000 →

(C:\WESTLAKE\WL240.GB0)

COLOG

(C:\WESTLAKE\WL241.GB0)

COLOG




---

**PVC Boring  
Downhole Gamma Logs**

---

(C:\WESTLAKE\PVC4.GB0)

COLOG



NGamma  
CPM


0 600000

(C:\WESTLAKE\PVC4.GB0)

COLOG

(C:\WESTLAKE\PVC5.GB0)

COLOG




NGamma CPM 0 600000

(C:\WESTLAKE\PVC5.GB0)

COLOG

**COLOG**




**COLOG**

(C:\WESTLAKE\PVC6.GBO)


COLOG

(C:\WESTLAKE\PVC7.GB0)



COLOG

(C:\WESTLAKE\PVC7.GB0)






(C:\WESTLAKE\PVC9.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →


(C:\WESTLAKE\PVC9.GB0)

COLOG

(C:\WESTLAKE\PVC1 0.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →


(C:\WESTLAKE\PVC1 0.GB0)

COLOG

(C:\WESTLAKE\PVC11 A.GB0)

COLOG

← 0 NGamma CPM 600000 →





← 0 NGamma CPM 600000 →

(C:\WESTLAKE\PVC11 A.GB0)

COLOG


(C:\WESTLAKE\PVC11B.GB0)

COLOG



(C:\WESTLAKE\PVC1 2.GB0)

COLOG



NGamma CPM 600000


(C:\WESTLAKE\PVC1 2.GB0)

COLOG

(C:\WESTLAKE\PVC1 3.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →


(C:\WESTLAKE\PVC1 3.GB0)

COLOG

(C:\WESTLAKE\PVC1 8.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →


(C:\WESTLAKE\PVC1 8.GB0)

COLOG

(C:\WESTLAKE\PVC19.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →

(C:\WESTLAKE\PVC19.GB0)


COLOG



(C:\WESTLAKE\PVC20.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →

(C:\WESTLAKE\PVC20.GB0)

COLOG

**COLOG**




**COLOG**

(C:\WESTLAKE\PVC25.GB0)

COLOG

← 0 NGamma CPM 600000 →




← 0 NGamma CPM 600000 →

(C:\WESTLAKE\PVC25.GB0)

COLOG

(C:\WESTLAKE\PVC26.GC0)

COLOG




NGamma CPM 0 600000

(C:\WESTLAKE\PVC26.GC0)

COLOG

COLOG




Timeline diagram showing the duration of the NGamma CPM signal. The timeline starts at 0 and ends at 600,000. The signal is labeled "NGamma CPM" above the timeline.

**COLOG**

(C:\WESTLAKE\PVC28.GB0)

COLOG



NGamma  
CPM

0 600000


(C:\WESTLAKE\PVC28.GB0)

COLOG

(C:\WESTLAKE\PVC33.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →


(C:\WESTLAKE\PVC33.GB0)

COLOG

(C:\WESTLAKE\PVC34.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →

(C:\WESTLAKE\PVC34.GB0)

COLOG



**COLOG**




(C:\WESTLAKE\PVC35.GB0)

(C:\WESTLAKE\PVC36.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →


(C:\WESTLAKE\PVC36.GB0)

COLOG

(C:\WESTLAKE\PVC37.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →


(C:\WESTLAKE\PVC37.GB0)

COLOG

(C:\WESTLAKE\PVC38.GB0)

COLOG

NGamma  
CPM 0 600000



NGamma  
CPM 0 600000


(C:\WESTLAKE\PVC38.GB0)

COLOG

(C:\WESTLAKE\PVC40.GB0)

COLOG

← 0 NGamma CPM 600000 →




← 0 NGamma CPM 600000 →

(C:\WESTLAKE\PVC40.GB0)

COLOG

**COLOG**




← 0 NGamma CPM 600000 →  
(C:\WESTLAKE\PVC41.GB0) **COLOG**

(C:\WESTLAKE\PVC41.GB0)

COLOG

← 0 NGamma CPM 600000 →



← 0 NGamma CPM 600000 →

(C:\WESTLAKE\PVC41.GB0)

COLOG

*Prepared for:*

The West Lake Respondent Group

*Prepared by:*


McLaren/Hart Environmental Engineering Corporation  
1000 Town Center, Suite 600  
Southfield, Michigan 48075

Prepared by:



Timothy C. Biggs  
Senior Associate Geoscientist

Reviewed by:



Bruce E. Ehleringer  
Managing Principal Geoscientist

November 26, 1996

Project No. 070803035

**GROUNDWATER CONDITIONS REPORT  
WEST LAKE LANDFILL RADIOLOGICAL  
AREAS 1 AND 2  
BRIDGETON, MISSOURI**



## **APPENDICES**

<b>Appendix A</b>	<b>Groundwater Analytical Results</b>
<b>Appendix B</b>	<b>Groundwater Priority Pollutant Analytical Results</b>
<b>Appendix C</b>	<b>QA/QC Analytical Reports</b>
<b>Appendix D</b>	<b>Boring Logs and Well Construction Details</b>
<b>Appendix E</b>	<b>MSD Disposal Acceptance Letters</b>
<b>Appendix F</b>	<b>Quanterra Laboratory Procedural Issue Memo and Letter</b>
<b>Appendix G</b>	<b>Aquifer Testing Results</b>

---

**Boring Logs and  
Well Construction Details**

---




# MONITORING WELL DETAILS

PROJECT NO. 070803035  
WELL NO. S-1

PROJECT NAME WEST LAKE LANDFILL  
WELL LOCATION BRIDGETON, MISSOURI

DATE 8/2/95 BY HART ENVIRONMENTAL DRILLING



## NOTES:

1. REFER TO SOIL BORING WL-204 FOR SOIL DESCRIPTION.
2. DETAIL NOT TO SCALE.
3. NM = NOT MEASURED




# MONITORING WELL DETAILS

PROJECT NO. 070803035  
WELL NO. 1-2

PROJECT NAME WEST LAKE LANDFILL  
WELL LOCATION BRIDGETON, MISSOURI

DATE 8/2/95 BY HART ENVIRONMENTAL DRILLING



## NOTES:

1. REFER TO SOIL BORING WL-205 FOR SOIL DESCRIPTION.
2. DETAIL NOT TO SCALE.
3. NM = NOT MEASURED
4. N/A NOT APPLICABLE. BENTONITE GROUT WAS USED TO SEAL WELL UP TO SURFACE.


MONITORING  
WELL DETAILS

PROJECT NO. 070803035  
WELL NO. D-3

PROJECT NAME WEST LAKE LANDFILL

WELL LOCATION BRIDGETON, MISSOURI

DATE 8/9/95 BY HART ENVIRONMENTAL DRILLING



NOTES:

1. REFER TO SOIL BORING WL-105A FOR SOIL DESCRIPTION.
2. DETAIL NOT TO SCALE.
3. NM = NOT MEASURED
4. N/A NOT APPLICABLE, BENTONITE GROUT/CHIPS USED TO SEAL WELL UP TO SURFACE.


MONITORING  
WELL DETAILS

PROJECT NO. 070803035  
WELL NO. 1-4

PROJECT NAME WEST LAKE LANDFILL

WELL LOCATION BRIDGETON, MISSOURI

DATE 8/10/95 BY HART ENVIRONMENTAL DRILLING



**NOTES:**

1. REFER TO SOIL BORING WL-105B FOR SOIL DESCRIPTION.
2. DETAIL NOT TO SCALE.
3. NM = NOT MEASURED
4. N/A NOT APPLICABLE, BENTONITE GROUT/CHIPS USED TO SEAL WELL UP TO SURFACE.


MONITORING  
WELL DETAILS

PROJECT NO. 070803035  
WELL NO. S-5

PROJECT NAME WEST LAKE LANDFILL

WELL LOCATION BRIDGETON, MISSOURI

DATE 8/15/95 BY HART ENVIRONMENTAL DRILLING



NOTES:

1. REFER TO SOIL BORING WL-105C FOR SOIL DESCRIPTION.
2. DETAIL NOT TO SCALE.
3. NM = NOT MEASURED


MONITORING  
WELL DETAILS

PROJECT NO. 070803035  
WELL NO. D-6

PROJECT NAME WEST LAKE LANDFILL

WELL LOCATION BRIDGETON, MISSOURI

DATE 8/17/95 BY HART ENVIRONMENTAL DRILLING



NOTES:

1. REFER TO SOIL BORING WL-206 SOIL DESCRIPTION.
2. DETAIL NOT TO SCALE.
3. NM = NOT MEASURED
4. N/A NOT APPLICABLE; BENTONITE GROUT USED TO SEAL WELL UP TO SURFACE




MONITORING  
WELL DETAILS

PROJECT NO. 070803035  
WELL NO. 1-7

PROJECT NAME WEST LAKE LANDFILL  
WELL LOCATION BRIDGETON, MISSOURI

DATE 8/3/95 BY HART  
ENVIRONMENTAL  
DRILLING



NOTES:

1. REFER TO SOIL BORING WL-207 SOIL DESCRIPTION.
2. DETAIL NOT TO SCALE.
3. NM = NOT MEASURED
4. N/A NOT APPLICABLE; BENTONITE GROUT USED TO SEAL WELL UP TO SURFACE


MONITORING  
WELL DETAILS

PROJECT NO. 070803035  
WELL NO. S-8

PROJECT NAME WEST LAKE LANDFILL

WELL LOCATION BRIDGETON, MISSOURI

DATE 9/15/95 BY HART ENVIRONMENTAL DRILLING



NOTES:


1. REFER TO SOIL BORING WL-228 FOR SOIL DESCRIPTION.
2. DETAIL NOT TO SCALE.
3. NM = NOT MEASURED.

# MONITORING WELL DETAILS

PROJECT NO. 070803035  
WELL NO. S-10

PROJECT NAME WEST LAKE LANDFILL  
WELL LOCATION BRIDGETON, MISSOURI

DATE 9/19/95 BY HART ENVIRONMENTAL DRILLING



## NOTES:


1. REFER TO SOIL BORING WL-216B FOR SOIL DESCRIPTION.
2. DETAIL NOT TO SCALE.
3. NM = NOT MEASURED.
4. N/A = NOT APPLICABLE; BENTONITE GROUT/CHIPS USED TO SEAL WELL UP TO SURFACE.

MONITORING  
WELL DETAILS

PROJECT NO. 070803035  
WELL NO. 1-11

PROJECT NAME WEST LAKE LANDFILL  
WELL LOCATION BRIDGETON, MISSOURI

DATE 10/13/95 BY HART ENVIRONMENTAL DRILLING



NOTES:


1. REFER TO SOIL BORING WL-216C FOR SOIL DESCRIPTION.
2. DETAIL NOT TO SCALE.
3. NM = NOT MEASURED.
4. N/A = NOT APPLICABLE; BENTONITE GROUT USED TO SEAL WELL UP TO SURFACE.

MONITORING  
WELL DETAILS

PROJECT NO. 070803035  
WELL NO. D-12

PROJECT NAME WEST LAKE LANDFILL  
WELL LOCATION BRIDGETON, MISSOURI

DATE 10/17/95 BY HART  
ENVIRONMENTAL  
DRILLING



NOTES:


1. REFER TO SOIL BORING WL-216A FOR SOIL DESCRIPTION.
2. DETAIL NOT TO SCALE.
3. NM = NOT MEASURED.
4. N/A = NOT APPLICABLE; BENTONITE GROUT USED TO SEAL WELL UP TO SURFACE.

# MONITORING WELL DETAILS

PROJECT NO. 070803035  
WELL NO. D-14

PROJECT NAME WEST LAKE LANDFILL  
WELL LOCATION BRIDGETON, MISSOURI


DATE 10/24/95 BY HART ENVIRONMENTAL DRILLING





## NOTES:

1. REFER TO SOIL BORING WL-109B FOR SOIL DESCRIPTION.
2. DETAIL NOT TO SCALE.
3. NM = NOT MEASURED.
4. \* = HYDRATED BENTONITE CHIPS USED TO SEAL WELL UP TO SURFACE.

# S-8 SLUG TEST DATA W/TELOG RECORDER



AQTESOLV

 GERAGHTY  
& MILLER, INC.  
 Modeling Group

---

## Aquifer Testing Results

---



**Aquifer Test Results**  
**West Lake Landfill, Bridgeton, Missouri**

Monitoring Well	Hydraulic Conductivity K (cm/s) *		
<b>Shallow Depth Wells</b>			
S-1	3.78E-03		
S-5	8.76E-04	Max	3.43E-02
S-8	3.43E-02	Min	8.76E-04
S-84	2.32E-03	Avg	8.22E-03
MW-101	4.17E-03		
MW-F3	3.83E-03		
<b>Intermediate Depth Wells</b>			
I-2	3.27E-02		
I-4	5.41E-02	Max	6.68E-02
I-7	6.68E-02	Min	1.22E-02
I-9	5.47E-02	Avg	4.45E-02
I-11	4.63E-02		
I-68	1.22E-02		
<b>Deep Depth Wells</b>			
D-3	3.15E-02		
D-6	4.29E-02	Max	8.85E-02
D-12	4.14E-02	Min	4.50E-03
D-13	8.85E-02	Avg	4.28E-02
D-85	4.50E-03		
D-93	4.78E-02		

\* All Hydraulic Conductivities were determined using the computer software program AQTESOLV™ (Geraghty & Miller, Inc. 1989). A graph of the data points was assigned a best fit line that was visually positioned on the graph.

**Equations for Determining Hydraulic Conductivity (K)  
using the Bouwer and Rice method**

$$K = \frac{r_c^2 \ln \left( \frac{R_e}{r_w} \right)}{2L_e} \frac{1}{t} \ln \frac{y_o}{y_t}$$

where  $r_c$  = radius of well casing  
 $L_e$  = length of well screen  
 $y_o$  = displacement at time 0  
 $y_t$  = displacement at time t

$$\ln \frac{R_e}{r_w} = \left[ \left( \frac{1.1}{\ln \frac{L_w}{r_w}} \right) + \left( \frac{A + B \ln \left[ \frac{(H - L_w)}{r_w} \right]}{\frac{L_e}{r_w}} \right) \right]^{-1}$$

where  $L_w$  = depth from potentiometric surface to bottom of well screen  
 $r_w$  = radial distance from center of well to native aquifer sediments  
 $H$  = saturated thickness of the aquifer  
 $A$  and  $B$  = constants taken from a plot in article entitled "the Bouwer and Rice Slug Test - An Update" by Herman Bouwer from Ground Water May-June 1989 Vol. 27, No. 3.

A semi-logarithmic plot of  $y$  and  $t$  with a best fit line drawn through the data will be plotted. The straight line drawn through the data will allow for selection of  $y_o$  and  $y_t$  to be substituted into equation 1. See next page for this plot for well S-8. Note this is where the "double straight line effect" will skew the value of  $K$  if the wrong part of the double line is chosen.

The use of the Hermit Data recorder will allow for collection of data in more frequent steps and will allow for data to be taken at quicker intervals. This increase in data will help in the decision of which of the double lines is correct for the aquifer conditions.

**RISING HEAD SLUG TEST**  
**DATA RECORDED WITH THE TELOG WLS-2109E DATA RECORDER**

DATE	TIME	MIN	AVG	MAX
12/12/95"	9:56:48	15.42	15.42	15.42
12/12/95"	9:56:49	14.96	14.96	14.96
12/12/95"	9:56:50	14.81	14.81	14.81
12/12/95"	9:56:51	14.96	14.96	14.96
12/12/95"	9:56:52	15.02	15.02	15.02
12/12/95"	9:56:53	15.33	15.33	15.33
12/12/95"	9:56:54	15.42	15.42	15.42
12/12/95"	9:56:55	15.39	15.39	15.39
12/12/95"	9:56:56	15.36	15.36	15.36
12/12/95"	9:56:57	15.37	15.37	15.37
12/12/95"	9:56:58	15.39	15.39	15.39

**BOUWER AND RICE CALCULATION DATA**

STATIC WATER LEVEL 13.02'  
 SCREEN LENGTH 20'  
 TOP OF SCREEN DEPTH 6.3'  
 BOTTOM OF SCREEN DEPTH 26.3'  
 BOTTOM OF AQUIFER DEPTH 109'  
 WELL DIAMETER 2"  
 DIAMETER OF FILTER PACK 4.25"

**ASSUMPTIONS**


Filter pack sand was placed through the middle of the auger  
 flites as the augers were pulled from the ground.

Assume the borehole collapsed around the filter pack  
 (see boring logs for the lithology of the native material)  
 therefore the radial distance from the center of the well  
 to the normal conductivity of the aquifer is 2.125"

Notice the "double straight line effect" from time 2 to 4 seconds and  
 again from 4 to 5 seconds. The data is too coarse to get the points  
 in between these two intervals for correct best fit line interpretation.  
 Without the best fit line, the correct value of K cannot be arrived at.

**DATA USED IN PLOT**

TIME	DISPACEMENT
1	0.46
2	0.61
3	0.46
4	0.4
5	0.09
6	0
7	0.03
8	0.03
9	0.02
10	0





JOHN ASHCROFT  
GOVERNOR

SP-1770-072011  
**MISSOURI DEPARTMENT OF HEALTH**

ROBERT HARMON, M.D.  
DIRECTOR

Site: <u>Westlake AL</u>
ID # <u>MBD07990932</u>
Break: <u>17.8</u>
Other: <u>5-13-87</u>

May 13, 1987

**RECEIVED**  
MAY 14 1987

WASTE MANAGEMENT  
PROGRAM

Mr. Keith Schardein, Chief  
Superfund Section  
Waste Management Program  
Missouri Department of Natural Resources  
P.O. Box 176  
Jefferson City, MO 65102

Dear Mr. Schardein: *Keith*

Re: Westlake Landfill Registry Site

Enclosed please find the documentation you requested about our source for contamination types and levels at the Westlake Landfill site. If you need more information concerning this site or have any other questions, please feel free to contact me at (314) 751-6102.

Sincerely,

*Gale M. Carlson*  
Gale M. Carlson  
Environmental Specialist  
Bureau of Environmental Epidemiology

GMC:v1h

enclosure

40241235



SUPERFUND RECORDS

Telephone: (314) 751-6400

P. O. Box 570

Jefferson City, MO 65102

AN EQUAL OPPORTUNITY/AFFIRMATIVE ACTION EMPLOYER  
services provided on a nondiscriminatory basis

DNR 0272

DOCUMENTATION RECORDS  
FOR  
HAZARD RANKING SYSTEM

INSTRUCTIONS: The purpose of these records is to provide a convenient way to prepare an auditable record of the data and documentation used to apply the Hazard Ranking System to a given facility. As briefly as possible summarize the information you used to assign the score for each factor (e.g., "Waste quantity = 4,230 drums plus 800 cubic yards of sludges"). The source of information should be provided for each entry and should be a bibliographic-type reference that will make the document used for a given data point easier to find. Include the location of the document and consider appending a copy of the relevant page(s) for ease in review.

FACILITY NAME: Westlake Landfill

LOCATION: \_\_\_\_\_

## GROUND WATER ROUTE

### 1 OBSERVED RELEASE

Contaminants detected (5 maximum):

None

Rationale for attributing the contaminants to the facility:

n/a

\* \* \*

### 2 ROUTE CHARACTERISTICS

#### Depth to Aquifer of Concern

Name/description of aquifers(s) of concern:

shallow alluvium of Missouri River

Depth(s) from the ground surface to the highest seasonal level of the saturated zone [water table(s)] of the aquifer of concern:

approximately 60 ft.

Depth from the ground surface to the lowest point of waste disposal/  
storage:

approximately 35 feet

Net Precipitation

Mean annual or seasonal precipitation (list months for seasonal):

approximately 36"

Mean annual lake or seasonal evaporation (list months for seasonal):

approximately 35"

Net precipitation (subtract the above figures):

+1"

Permeability of Unsaturated Zone

Soil type in unsaturated zone:

silty sands over limestone

Permeability associated with soil type:

approximately  $10^{-3}$  to  $10^{-5}$  cm/sec.

Physical State

Physical state of substances at time of disposal (or at present time for generated gases):

liquid

\*\*\*

### 3 CONTAINMENT

#### Containment

Method(s) of waste or leachate containment evaluated:

Landfill; no liner; some ponding

Method with highest score:

above

### 4 WASTE CHARACTERISTICS

#### Toxicity and Persistence

Compound(s) evaluated:

Chlordane  
TCE  
Toluene

Compound with highest score:

Chlordane

#### Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):

4000 tons Pesticides  
7000 tons Low-level uranium  
Undetermined amounts of waste solvents

Basis of estimating and/or computing waste quantity:

"Superfund Notifications"  
Interviews and Company records

\* \* \*



5 TARG.

Ground Water Use

Use(s) of aquifer(s) of concern within a 3-mile radius of the facility:

Commercial with municipal water available.

Distance to Nearest Well

Location of nearest well drawing from aquifer of concern or occupied building not served by a public water supply:

Not used for drinking water

Distance to above well or building:

n/a

Population Served by Ground Water Wells Within a 3-Mile Radius

Identified water-supply well(s) drawing from aquifer(s) of concern within a 3-mile radius and populations served by each:

n/a

Computation of land area irrigated by supply well(s) drawing from aquifer(s) of concern within a 3-mile radius, and conversion to population (1.5 people per acre):

n/a

Total population served by ground water within a 3-mile radius:

None

## SURFACE WATER ROUTE

### 1 OBSERVED RELEASE

Contaminants detected in surface water at the facility or downhill from it (5 maximum):

None

Rationale for attributing the contaminants to the facility:

n/a

\* \* \*

### 2 ROUTE CHARACTERISTICS

#### Facility Slope and Intervening Terrain

Average slope of facility in percent:

greater than 8% slope

Name/description of nearest downslope surface water:

Missouri River

Average slope of terrain between facility and above-cited surface water body in percent:

between 3 and 5% slope

Is the facility located either totally or partially in surface water?

No

Is the facility completely surrounded by areas of higher elevation?

No

1-Year 24-Hour Rainfall in Inches

between 2.5-30 inches

Distance to Nearest Downslope Surface Water

between 1 and 2 miles

Physical State of Waste

liquids

\* \* \*

### 3 CONTAINMENT

#### Containment

Method(s) of waste or leachate containment evaluated:

Landfill, diversion system unsound

Method with highest score:

above

#### 4 WASTE CHARACTERISTICS

##### Toxicity and Persistence

Compound(s) evaluated

See groundwater

Compound with highest score:

see groundwater

##### Hazardous Waste Quantity

Total quantity of hazardous substances at the facility, excluding those with a containment score of 0 (Give a reasonable estimate even if quantity is above maximum):

see groundwater

Basis of estimating and/or computing waste quantity:

see groundwater

\* \* \*

#### 5 TARGETS

##### Surface Water Use

Use(s) of surface water within 3 miles downstream of the hazardous substance:

Recreation

Is there tidal influence?

No

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

n/a

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

n/a

Distance to critical habitat of an endangered species or national wildlife refuge, if 1 mile or less:

n/a

Population Served by Surface Water

Location(s) of water-supply intake(s) within 3 miles (free-flowing bodies) or 1 mile (static water bodies) downstream of the hazardous substance and population served by each intake:

None

Computa. of land area irrigated by above-cited intake(s)  
conversion to population (1.5 people per acre):

n/a

Total population served:

None

Name/description of nearest of above water bodies:

Missouri River

Distance to above-cited intakes, measured in stream miles.

n/a

AIR ROUTE

1 OBSERVED RELEASE

Contaminants detected:

None

Date and location of detection of contaminants

n/a

Methods used to detect the contaminants:

n/a

Rationale for attributing the contaminants to the site:

n/a

\*\*\*

2 WASTE CHARACTERISTICS

Reactivity and Incompatibility

Most reactive compound:

n/a

Most incompatible pair of compounds:

n/a

Toxicity

Most toxic compound:

n/a

Hazardous Waste Quantity

Total quantity of hazardous waste:

n/a

Basis of estimating and/or computing waste quantity:

n/a

\* \* \*

3 TARGETS

Population Within 4-Mile Radius

Circle radius used, give population, and indicate how determined:

0 to 4 mi

0 to 1 mi

0 to 1/2 mi

0 to 1/4 mi

n/a

Distance to a Sensitive Environment

Distance to 5-acre (minimum) coastal wetland, if 2 miles or less:

n/a

Distance to 5-acre (minimum) fresh-water wetland, if 1 mile or less:

n/a



Distance to critical habitat of an endangered species, if 1 mile or less:

n/a

Land Use

Distance to commercial/industrial area, if 1 mile or less:

n/a

Distance to national or state park, forest, or wildlife reserve, if 2 miles or less:

n/a

Distance to residential area, if 2 miles or less:

n/a

Distance to agricultural land in production within past 5 years, if 1 mile or less:

n/a

Distance to prime agricultural land in production within past 5 years, if 2 miles or less:

n/a

Is a historic or landmark site (National Register or Historic Places and National Natural Landmarks) within the view of the site?

n/a



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT

SITE NUMBER (to be assigned by HQ)

1475

GENERAL INSTRUCTIONS: Complete Sections I and III through XV of this form as completely as possible. Then use the information on this form to develop a Tentative Disposition (Section II). File this form in its entirety in the regional Hazardous Waste Log File. Be sure to include all appropriate Supplemental Reports in the file. Submit a copy of the forms to: U.S. Environmental Protection Agency; Site Tracking System; Hazardous Waste Enforcement Task Force (EN-335); 401 M St., SW; Washington, DC 20460.

I. SITE IDENTIFICATION

A. SITE NAME <u>WESTLAKE QUARRY LANDFILL</u>		B. STREET (or other identifier) <u>Rt. 1 Box 206</u>	
C. CITY <u>Bridgeton</u>	D. STATE <u>Mo.</u>	E. ZIP CODE <u>63044</u>	F. COUNTY NAME <u>St. Louis</u>
G. SITE OPERATOR INFORMATION		3. TELEPHONE NUMBER	
1. NAME <u>William CANNY</u>		<u>314 739-1122</u>	
2. STREET <u>Rt. 1 Box 206</u>		4. CITY <u>Bridgeton</u>	5. STATE <u>Mo.</u>
			6. ZIP CODE <u>63042</u>
H. REALTY OWNER INFORMATION (if different from operator of site)			
1. NAME <u>ESTATE OF V.R. CRUSE - CATHERINE CRUSE AND L.E. TRAPP</u>		2. TELEPHONE NUMBER <u>314 739-1122</u>	
A PARTNERSHIP.			
3. CITY <u>Rt. 1 Box 206 Bridgeton</u>		4. STATE <u>Mo.</u>	5. ZIP CODE <u>63042</u>
I. SITE DESCRIPTION <u>STATE APPROVED SANITARY AND DEMOLITION LANDFILLS</u>			
J. TYPE OF OWNERSHIP			
<input type="checkbox"/> 1. FEDERAL <input type="checkbox"/> 2. STATE <input type="checkbox"/> 3. COUNTY <input type="checkbox"/> 4. MUNICIPAL <input checked="" type="checkbox"/> 5. PRIVATE			

II. TENTATIVE DISPOSITION (complete this section last)

A. ESTIMATE DATE OF TENTATIVE DISPOSITION (mo., day, & yr.)	B. APPARENT SERIOUSNESS OF PROBLEM
	<input type="checkbox"/> 1. HIGH <input checked="" type="checkbox"/> 2. MEDIUM <input type="checkbox"/> 3. LOW <input type="checkbox"/> 4. NONE
C. PREPARER INFORMATION	
1. NAME <u>Robert PAPPENFORT</u>	2. TELEPHONE NUMBER <u>314 751-3241</u>
3. DATE (mo., day, & yr.) <u>12/10/79</u>	

III. INSPECTION INFORMATION

A. PRINCIPAL INSPECTOR INFORMATION		4. TELEPHONE NO. (area code & no.)	
1. NAME <u>MIKE DWALL (5/31/79)</u> <u>HOWARD WINBURN (2/2/79)</u>		<u>ENVIRONMENTAL SPECIALIST</u> <u>ENVIRONMENTAL ENGINEER</u>	
2. ORGANIZATION <u>Mo. DEPARTMENT of NATURAL RESOURCES</u>		<u>314 849-1313</u>	
B. INSPECTION PARTICIPANTS			
1. NAME	2. ORGANIZATION	3. TELEPHONE NO.	
<u>SAME AS ABOVE.</u>			

1. NAME	2. TITLE & TELEPHONE NO.	3. ADDRESS
<u>Mr. William CANNY</u>	<u>Site OPERATOR</u> <u>314 739-1122</u>	<u>Rt. 1 Box 206</u> <u>Bridgeton, Mo. 63042</u>

C. SITE REPRESENTATIVES INTERVIEWED (corporate officials, workers, residents)

1. NAME	2. TITLE & TELEPHONE NO.	3. ADDRESS
<u>Mr. William CANNY</u>	<u>Site OPERATOR</u> <u>314 739-1122</u>	<u>Rt. 1 Box 206</u> <u>Bridgeton, Mo. 63042</u>

## III. INSPECTION INFORMATION (continued)

D. GENERATOR INFORMATION (source of waste)			
1. NAME	2. TELEPHONE NO.	3. ADDRESS	4. WASTE TYPE GENERATED
Borden Chemical Printing Ink Div.	314 991-2544	1185 RIVERCH St. Louis, Mo. 63132	WASTE INK, Pigment Oily Sludges, Ester
Cherlean Chemical Co.	314 432-8234	2497 Adie Road Maryland Heights, Mo. 63043	Insecticides, Herbicides, Fertilizers, etc.
Piasek, Inc.	618-271-4800	423 West 55th Street New York, New York 10019	WASTEWATER Sludge FROM E. ST. LOUIS

E. TRANSPORTER/HAULER INFORMATION			
1. NAME	2. TELEPHONE NO.	3. ADDRESS	4. WASTE TYPE TRANSPORTED

## F. IF WASTE IS PROCESSED ON SITE AND ALSO SHIPPED TO OTHER SITES, IDENTIFY OFF-SITE FACILITIES USED FOR DISPOSAL.

1. NAME	2. TELEPHONE NO.	3. ADDRESS

G. DATE OF INSPECTION (mo., day, & yr.) 2/2/79  
5/5/79 H. TIME OF INSPECTION DAYTIME I. ACCESS GAINED BY: (credentials must be shown in all cases)  
☒ 1. PERMISSION ☐ 2. WARRANT

J. WEATHER (describe)

N/A.

## IV. SAMPLING INFORMATION

A. Mark 'X' for the types of samples taken and indicate where they have been sent e.g., regional lab, other EPA lab, contractor, etc. and estimate when the results will be available.

1. SAMPLE TYPE	2. SAMPLE TAKEN (mark 'X')	3. SAMPLE SENT TO:	4. DATE RESULTS AVAILABLE
a. GROUNDWATER	X	ALL 9 Monitoring Wells sampled	6/12/79
b. SURFACE WATER		Four Groundwater Wells Sampled in Early 1979	See DNR File
c. WASTE			
d. AIR			
e. RUNOFF			
f. SPILL			
g. SOIL	X	33 test borings made in 1973.	See ENG. PLANS - Mo.
h. VEGETATION			
i. OTHER (specify) LEACHATE	1/23/78	MSD - St. Louis	See DNR File

## B. FIELD MEASUREMENTS TAKEN (e.g., radioactivity, explosivity, PH, etc.)

1. TYPE	2. LOCATION OF MEASUREMENTS	3. RESULTS

## VI. WASTE RELATED INFORMATION (continued)

2. Estimate the amount (specify unit of measure) of waste by category; mark 'X' to indicate which are present.		3. Estimate the amount (specify unit of measure) of waste by category; mark 'X' to indicate which are present.		4. Estimate the amount (specify unit of measure) of waste by category; mark 'X' to indicate which are present.		5. Estimate the amount (specify unit of measure) of waste by category; mark 'X' to indicate which are present.		6. Estimate the amount (specify unit of measure) of waste by category; mark 'X' to indicate which are present.			
a. SLUDGE		b. OIL		c. SOLVENTS		d. CHEMICALS		e. SOLIDS		f. OTHER	
AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE	AMOUNT	UNIT OF MEASURE
		Unknown				4000		2100		UNKNOWN	
						tons		tons		UNKNOWN	
(1) PAINT, PIGMENTS	X	(1) OILY WASTES	X	(1) HALOGENATED SOLVENTS	X	(1) ACIDS	X	(1) FLYASH	X	(1) LABORATORY, PHARMACEUT.	
(2) METALS SLUDGES	X	(2) OTHER (specify):	X	(2) NON-HALOGENATED SOLVENTS		(2) PICKLING LIQUORS		(2) ASBESTOS		(2) HOSPITAL	
(3) POTW		Int. Sludge		(3) OTHER (specify):		(3) CAUSTICS	X	(3) MILLING/MINE TAILINGS SLUDGE	X	(3) RADIOACTIVE (LOW LEVEL)	
(4) ALUMINUM SLUDGE						(4) PESTICIDES	X	(4) FERROUS SMELTING WASTES		(4) MUNICIPAL	
(5) OTHER (specify):						(5) DYES/INKS		(5) NON-FERROUS SMELTING WASTES		(5) OTHER (specify):	
						(6) CYANIDE		(6) OTHER (specify):		Waste Ore Residuals from Old Cotter Corporation, Laddie Avenue St. Louis, Mo.	
						(7) PHENOLS					
						(8) HALOGENS - AROMATICS	X				
						(9) PCB					
						(10) METALS	X				
						(11) OTHER (specify):					

## D. LIST SUBSTANCES OF GREATEST CONCERN WHICH ARE ON THE SITE (place in descending order of hazard)

1. SUBSTANCE	2. FORM (mark 'X')			3. TOXICITY (mark 'X')				4. CAS NUMBER	5. AMOUNT	6. UNIT
	a. SOLID	b. LIQ.	c. VAPOUR	a. HIGH	b. MED.	c. LOW	d. NONE			
Pesticides - Herbicide Residues	X								4000	tons
Low Level Rad. Wastes	X								?	tons

## VIII. HAZARD DESCRIPTION

FIELD EVALUATION HAZARD DESCRIPTION: Place an 'X' in the box to indicate that the listed hazard exists. Describe the hazard in the space provided.

☐ A. HUMAN HEALTH HAZARDS

## IV. SAMPLING INFORMATION (continued)

## C. PHOTOS

## 1. TYPE OF PHOTOS

☐ 1. GROUND ☒ 2. AERIAL

## 2. PHOTOS IN CUSTODY OF:

Mo. DNR - See Engineering Plans

## D. SITE MAPPED?

☒ YES. SPECIFY LOCATION OF MAPS:

## E. COORDINATES

1. ~~Latitude (degrees, minutes, seconds)~~2. ~~Longitude (degrees, minutes, seconds)~~

Sec. 131 T47N R5E St. Louis County

## V. SITE INFORMATION

## A. SITE STATUS

☒ 1. ACTIVE (Those industrial or municipal sites which are being used for waste treatment, storage, or disposal on a continuing basis, even if infrequently.)

☐ 2. INACTIVE (Those sites which no longer receive wastes.)

☐ 3. OTHER (specify):  
(Those sites that include such incidents like "midnight dumping" where no regular or continuing use of the site for waste disposal has occurred.)

## B. IS GENERATOR ON SITE?

☒ 1. NO ☐ 2. YES (specify generator's four-digit SIC Code):

## C. AREA OF SITE (in acres)

 Site 1 - 25 acres  
 Site 2 - 13 acres

## D. ARE THERE BUILDINGS ON THE SITE?

☐ 1. NO ☒ 2. YES (specify): Quarry Buildings for Plant

## VI. CHARACTERIZATION OF SITE ACTIVITY

Indicate the major site activity(ies) and details relating to each activity by marking 'X' in the appropriate boxes.

<input checked="" type="checkbox"/> A. TRANSPORTER	<input type="checkbox"/> B. STORER	<input checked="" type="checkbox"/> C. TREATER	<input checked="" type="checkbox"/> D. DISPOSER
1. RAIL	1. PILE	1. FILTRATION	<input checked="" type="checkbox"/> 1. LANDFILL
2. SHIP	2. SURFACE IMPOUNDMENT	2. INCINERATION	2. LANDFARM
3. BARGE	3. DRUMS	3. VOLUME REDUCTION	3. OPEN DUMP
4. TRUCK	4. TANK, ABOVE GROUND	4. RECYCLING/RECOVERY	4. SURFACE IMPOUNDMENT
5. PIPELINE	5. TANK, BELOW GROUND	5. CHEM/PHYS./TREATMENT	5. MIDNIGHT DUMPING
6. OTHER (specify):	6. OTHER (specify):	6. BIOLOGICAL TREATMENT	6. INCINERATION
		7. WASTE OIL REPROCESSING	7. UNDERGROUND INJECTION
		8. SOLVENT RECOVERY	8. OTHER (specify):
		9. OTHER (specify):	

E. SUPPLEMENTAL REPORTS: If the site falls within any of the categories listed below, Supplemental Reports must be completed. Indicate which Supplemental Reports you have filled out and attached to this form.

☐ 1. STORAGE ☐ 2. INCINERATION ☒ 3. LANDFILL ☐ 4. SURFACE IMPOUNDMENT ☐ 5. DEEP WELL  
☐ 6. CHEM/BIO/PHYS TREATMENT ☐ 7. LANDFARM ☐ 8. OPEN DUMP ☐ 9. TRANSPORTER ☐ 10. RECYCLOR/RECLAIMER

## VII. WASTE RELATED INFORMATION

## A. WASTE TYPE

☐ 1. LIQUID ☒ 2. SOLID ☒ 3. SLUDGE ☐ 4. GAS

## B. WASTE CHARACTERISTICS

☐ 1. CORROSIVE ☒ 2. IGNITABLE ☒ 3. RADIOACTIVE ☐ 4. HIGHLY VOLATILE  
☒ 5. TOXIC ☐ 6. REACTIVE ☐ 7. INERT ☐ 8. FLAMMABLE

## C. WASTE CATEGORIES

1. Are records of wastes available? Specify items such as manifests, inventories, etc. below.

## VIII. HAZARD DESCRIPTION (continued)

☐ N. FIRE OR EXPLOSION☒ O. SPILLS/LEAKING CONTAINERS/RUNOFF STANDING LIQUID

*In quarry from seepage from west wall. (2/2/79)*

☒ P. SEWER, STORM DRAIN PROBLEMS

*Significant Amount of Water Intrusion Occurring in the West Wall of the Quarry. (5/31/79)*

☒ Q. EROSION PROBLEMS

*Area near side slope near the original leachate collection well has some erosion. (5/31/79)*

☐ R. INADEQUATE SECURITY☒ S. INCOMPATIBLE WASTES

*Much non-demolition material was placed in the demolition landfill.*

# VIII. HAZARD DESCRIPTION (continued)

☐ T. MIDNIGHT DUMPING

☐ U. OTHER (specify):

## IX. POPULATION DIRECTLY AFFECTED BY SITE

A. LOCATION OF POPULATION	B. APPROX. NO. OF PEOPLE AFFECTED	C. APPROX. NO. OF PEOPLE AFFECTED WITHIN UNIT AREA	D. APPROX. NO. OF BUILDINGS AFFECTED	E. DISTANCE TO SITE (specify units)
1. IN RESIDENTIAL AREAS	<i>1 occupied residence in the neighborhood</i>			
2. IN COMMERCIAL OR INDUSTRIAL AREAS				
3. IN PUBLICLY TRAVELLED AREAS	<i>NEAR Interstate 70</i>	<i>(4000 ±)</i>		
4. PUBLIC USE AREAS (parks, schools, etc.)				

## X. WATER AND HYDROLOGICAL DATA

A. DEPTH TO GROUNDWATER (specify unit) <i>Water Table 440' elev</i>	B. DIRECTION OF FLOW <i>Westward to Missouri River</i>	C. GROUNDWATER USE IN VICINITY
D. POTENTIAL YIELD OF AQUIFER <i>N/A</i>	E. DISTANCE TO DRINKING WATER SUPPLY (specify unit of measure) <i>2 miles to Mo. River</i>	F. DIRECTION TO DRINKING WATER SUPPLY <i>West</i>
G. TYPE OF DRINKING WATER SUPPLY		
<input type="checkbox"/> 1. NON-COMMUNITY < 15 CONNECTIONS <input type="checkbox"/> 2. COMMUNITY (specify town): _____ > 15 CONNECTIONS		
<input checked="" type="checkbox"/> 3. SURFACE WATER <input type="checkbox"/> 4. WELL		

Continued From Page 2

## X. WATER AND HYDROLOGICAL DATA (continued)

## H. LIST ALL DRINKING WATER WELLS WITHIN A 1/4 MILE RADIUS OF SITE

1. WELL	2. DEPTH (specify unit)	3. LOCATION (proximity to population/buildings)	4. NON-COM- MUNITY (mark 'X')	5. COMMUN- ITY (mark 'X')
<i>See Missouri Geological Survey, RHA, Mo.</i>				

## I. RECEIVING WATER

## 1. NAME

*Missouri River*☐ 2. SEWERS☒ 3. STREAMS/RIVERS☐ 4. LAKES/RESERVOIRS☐ 5. OTHER (specify):

## 6. SPECIFY USE AND CLASSIFICATION OF RECEIVING WATERS

## XI. SOIL AND VEGETATION DATA

## LOCATION OF SITE IS IN:

☐ A. KNOWN FAULT ZONE☐ B. KARST ZONE☒ C. *Missouri River Alluvium*  
100-YEAR FLOOD PLAIN☐ D. WETLAND☐ E. A REGULATED FLOODWAY☐ F. CRITICAL HABITAT☐ G. RECHARGE ZONE OR SOLE SOURCE AQUIFER

## XII. TYPE OF GEOLOGICAL MATERIAL OBSERVED

Mark 'X' to indicate the type(s) of geological material observed and specify where necessary, the component parts.

'X'	A. C. VERBURDEN	'X'	B. BEDROCK (specify below)	'X'	C. OTHER (specify below)
X	1. SAND - SILT (60')			X	Groundwater @ 20-30'
X	2. CLAY (Moist)				or 440' elevation
	3. GRAVEL				

## XIII. SOIL PERMEABILITY

☐ A. UNKNOWN☐ B. VERY HIGH (100,000 to 1000 cm/sec.)☐ C. HIGH (1000 to 10 cm/sec.)☐ D. MODERATE (10 to .1 cm/sec.)☒ E. <sup>HIGH</sup>LOW (.1 to .001 cm/sec.)☐ F. VERY LOW (.001 to .00001 cm/sec.)

## G. RECHARGE AREA

☒ 1. YES☐ 2. NO

3. COMMENTS:

## H. DISCHARGE AREA

☐ 1. YES☐ 2. NO

3. COMMENTS:

## I. SLOPE

1. ESTIMATE % OF SLOPE

*50/12,000*

2. SPECIFY DIRECTION OF SLOPE, CONDITION OF SLOPE, ETC.

*WESTWARD*

## J. OTHER GEOLOGICAL DATA



## XIV. PERMIT INFORMATION

List all applicable permits held by the site and provide the related information.

A. PERMIT TYPE (e.g., RCRA, State, NPDES, etc.)	B. ISSUING AGENCY	C. PERMIT NUMBER	D. DATE ISSUED (mo., day, & yr.)	E. EXPIRATION DATE (mo., day, & yr.)	F. IN COMPLIANCE (mark 'X')		
					1. YES	2. NO	3. UN- KNOWN
State (25 acres)	Mo. Div. of Health	118903 218903	8/27/74				
State (13 acres)	Mo. DNR	118906	1/22/79	N/A			

## XV. PAST REGULATORY OR ENFORCEMENT ACTIONS

☐ NONE      ☐ YES (summarize in this space)

NOTE: Based on the information in Sections III through XV, fill out the Tentative Disposition (Section II) information on the first page of this form.

**LANDFILLS SITE INSPECTION REPORT**  
(Supplemental Report)

**INSTRUCTION**  
Answer and Explain  
as Necessary.

1. EVIDENCE OF SITE INSTABILITY (Erosion, Settling, Sink Holes, etc)

☒ YES ☐ NO

2. EVIDENCE OF IMPROPER DISPOSAL OF BULK LIQUIDS, SEMI-SOLIDS AND SLUDGES INTO THE LANDFILL

☒ YES ☐ NO

3. CHECK RECORDS OF CELL LOCATION AND CONTENTS AND BENCHMARK

☐ YES ☒ NO

4. WASTES SURROUNDED BY SORBENT MATERIAL

☐ YES ☒ NO

5. DIVERSION STRUCTURES ARE EFFECTIVELY CONSTRUCTED AND PROPERLY MAINTAINED

☐ YES ☐ NO

6. EVIDENCE OF PONDING OF WATER ON SITE

☒ YES ☐ NO

7. EVIDENCE OF IMPROPER/INADEQUATE DRAINING

☒ YES ☐ NO

8. ADEQUATE LEACHATE COLLECTION SYSTEM (If "Yes", specify Type)

☐ YES ☒ NO

8a. SURFACE LEACHATE SPRING

☒ YES ☐ NO

*West Wall of Quarry*

9. RECORDS OF LEACHATE ANALYSIS

☒ YES ☐ NO

*"One"*

10. GAS MONITORING

☒ YES ☐ NO

11. GROUNDWATER MONITORING WELLS

☒ YES ☐ NO

*Total of Nine*

12. ARTIFICIAL MEMBRANE LINER INSTALLED

☐ YES ☒ NO

13. SPECIFIC CONTAINMENT MEASURES (Clay Bottom, Sides, etc)

☒ YES ☐ NO

*Clay Pad (24" Compacted)*

14. FIXATION (Stabilization) OF WASTE

☐ YES ☒ NO

15. ADEQUATE CLOSURE OF INACTIVE PORTION OF FACILITY

☐ YES ☒ NO

16. COVER (Type)

*Daily 6" clay cover plus 24 inches final cover over filled areas.*

16a. THICKNESS



16b. PERMEABILITY

*UNKNOWN*

16c. DAILY APPLICATION

☒ YES ☐ NO

*For sanitary landfill  
Once per week for demolition fill*